

AD-A156 743


NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
LAKE PARAN (VT 000081... (U) CORPS OF ENGINEERS WALTHAM
MA NEW ENGLAND DIV AUG 78


1/2

UNCLASSIFIED

F/G 13/13

NL





AD-A156 743

SECTION REPORT
SPECTION PROG



S. 10

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER VT 00006	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Lake Paran NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
		6. PERFORMING ORG. REPORT NUMBER
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		8. CONTRACT OR GRANT NUMBER(s)
9. PERFORMING ORGANIZATION NAME AND ADDRESS		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		12. REPORT DATE August 1978
		13. NUMBER OF PAGES 53
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Hudson River Basin North Bennington, VT Paran Creek		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The dam is about 29 ft. high and 550 ft. long. On the day of the inspection, a 7 ft. diameter hole was found just below water level on the upstream side. It is recommended that the lake level be maintained at the invert of the gate structure. The dam would be overtopped by 3.3 ft. during the test flood ($\frac{1}{2}$ PMF).		

LAKE PARAN DAM



VT00006

NORTH BENNINGTON, VERMONT

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

Accession For	
NTIS GRA&I	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A/	23

DTIC
COPY
INSPECTED
1



Walter A. Henry

NATIONAL DAM INSPECTION PROGRAM
PHASE I INSPECTION REPORT

Identification No.: VT 00006
Name of Dam: Lake Paran
Town: North Bennington
County and State: Bennington County, Vermont
Stream: Paran Creek
Date of Inspection: June 22, 1978

STATEMENT OF SIGNIFICANT FINDINGS AND BRIEF ASSESSMENT

This dam is about 29 feet high and 550 feet long. It was presumably constructed of glacial till between 1851 and 1855. Within about one year, it reportedly failed - killing one person - and was subsequently rebuilt. At the left side of the embankment there is a 90-foot long spillway with its crest 3.3 feet below the top of the dam. The water level on the day of inspection was just above the spillway crest. At the right end there is an inoperable gated outlet structure with invert 14.8 feet below the top of the dam and a 4-foot diameter corrugated metal pipe outlet. Heavy shrubs and trees cover the downstream slope, and shrubs are growing from the riprap upstream.

On the day of inspection, June 22, 1978, a 7-foot diameter hole was found just below water level on the upstream side. This hole tapered to a diameter of about 4 feet at a depth of 7 to 10 feet. Water was flowing into the hole, and a 1-inch diameter vortex formed intermittently near the middle of the hole. Thousands of gallons per minute of flow were observed exiting from the toe of the dam and up to 3 feet above the toe. The flow into the hole was estimated to be no more than 1/2 to 2/3 of the flow rate observed downstream.

The Corps of Engineers was notified of the hole in the morning on June 23, 1978 at which time the inspectors recommended that the lake be drained immediately below the level of the hole, or lower, as necessary to essentially eliminate seepage. A crew of two men was left on the dam on June 24 and 25. On June 26, 1978 the watch was assumed by the Chairman of the Board of Trustees, North Bennington, who began operations to lower the lake level on that day.

STATEMENT OF RECOMMENDED ACTION

It is recommended that the lake level be maintained at the invert of the gate structure, that the gate be left open, and that a carefully designed warning system be established and tested to allow evacuation of the downstream areas before the lake level rises to within 6 feet below the top of the dam. In addition immediate steps should be undertaken to provide additional outlets, since the dam would be overtopped by 3.3 feet during the test flood (1/2 PMF).

NATIONAL DAM INSPECTION PROGRAM
PHASE I INSPECTION REPORT

Identification No.: VT 00060
Name of Dam: Lake Paran
Town: North Bennington
County and State: Bennington County, Vermont
Stream: Paran Creek
Date of Inspection: June 22, 1978

STATEMENT OF SIGNIFICANT FINDINGS AND BRIEF ASSESSMENT

This dam is about 29 feet high and 550 feet long. It was presumably constructed of glacial till between 1851 and 1855. Within about one year, it reportedly failed - killing one person - and was subsequently rebuilt. At the left side of the embankment there is a 90-foot long spillway with its crest 3.3 feet below the top of the dam. The water level on the day of inspection was just above the spillway crest. At the right end there is an inoperable gated outlet structure with invert 14.8 feet below the top of the dam and a 4-foot diameter corrugated metal pipe outlet. Heavy shrubs and trees cover the downstream slope, and shrubs are growing from the riprap upstream.

On the day of inspection, June 22, 1978, a 7-foot diameter hole was found just below water level on the upstream side. This hole tapered to a diameter of about 4 feet at a depth of 7 to 10 feet. Water was flowing into the hole, and a 1-inch diameter vortex formed intermittently near the middle of the hole. Thousands of gallons per minute of flow were observed exiting from the toe of the dam and up to 3 feet above the toe. The flow into the hole was estimated to be no more than 1/2 to 2/3 of the flow rate observed downstream.

The Corps of Engineers was notified of the hole in the morning on June 23, 1978 at which time the inspectors recommended that the lake be drained immediately below the level of the hole, or lower, as necessary to essentially eliminate seepage. A crew of two men was left on the dam on June 24 and 25. On June 26, 1978 the watch was assumed by the Chairman of the Board of Trustees, North Bennington, who began operations to lower the lake level on that day.

STATEMENT OF RECOMMENDED ACTION

It is recommended that the lake level be maintained at the invert of the gate structure, that the gate be left open, and that a carefully designed warning system be established and tested to allow evacuation of the downstream areas before the lake level rises to within 6 feet below the top of the dam. In addition immediate steps should be undertaken to provide additional outlets, since the dam would be overtopped by 3.3 feet during the test flood (1/2 PMF).

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.


Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

TABLE OF CONTENTS

	<u>Page</u>
REVIEW BOARD PAGE	iii
PREFACE	iv
TABLE OF CONTENTS	v
TABLE OF CONTENTS	vi
TABLE OF CONTENTS	vii
OVERVIEW PHOTO	viii
LOCATION MAP	ix
REPORT	
SECTION 1 - PROJECT INFORMATION	1
1.1 GENERAL	1
a. Authority	1
b. Purpose	1
1.2 DESCRIPTION OF PROJECT	1
a. Location	1
b. Description of Dam and Appurtenances	1
c. Size Classification	2
d. Hazard Classification	2
e. Ownership	2
f. Operator	2
g. Purpose	2
h. Design and Construction History	2
i. Normal Operation Procedure(s)	3
1.3 PERTINENT DATA	3
a. Drainage Area	3
b. Discharge at Dam Site	3

	<u>Page</u>
c. Elevation	4
d. Reservoir	4
e. Storage	4
f. Reservoir Surface	4
g. Dam	5
i. Spillway	5
j. Regulating Outlets	6
SECTION 2 - ENGINEERING DATA	7
2.1 DESIGN	7
2.2 CONSTRUCTION	7
2.3 OPERATION	7
2.4 EVALUATION	7
a. Availability	7
b. Adequacy	7
c. Validity	7
SECTION 3 - VISUAL INSPECTION	8
3.1 FINDINGS	8
a. General	8
b. Dam	8
c. Appurtenant Structures	9
d. Reservoir Area	10
e. Downstream Channel	10
3.2 EVALUATION	11
SECTION 4 - OPERATIONAL PROCEDURES	12
4.1 PROCEDURES	12
4.2 MAINTENANCE OF DAM	12
4.3 MAINTENANCE OF OPERATING FACILITIES	12
4.4 DESCRIPTION OF WARNING SYSTEM IN EFFECT	12
4.5 EVALUATION	12
SECTION 5 - HYDRAULIC AND HYDROLOGIC EVALUATION	13
5.1 EVALUATION OF FEATURES	13
a. Design Data	13
b. Experience Data	13
c. Visual Observation	13
d. Overtopping Potential	13

	<u>Page</u>
SECTION 6 - STRUCTURAL STABILITY	14
6.1 EVALUATION OF STRUCTURAL STABILITY	14
a. Visual Observations	14
b. Design and Construction Data	14
c. Operating Records for the Dam	14
d. Post-Construction Changes	14
e. Seismic Stability	14
SECTION 7 - ASSESSMENT, RECOMMENDATIONS/REMEDIAL MEASURES	15
7.1 DAM ASSESSMENT	15
a. Condition	15
b. Adequacy of Information	15
c. Urgency	15
d. Necessity for Additional Investigations	15
7.2 RECOMMENDATIONS	16
7.3 REMEDIAL MEASURES	16
a. Alternatives	16
b. O & M Maintenance & Procedures	16
APPENDIX A	
Visual Inspection Check List	
APPENDIX B	
Project Records and Plans	
APPENDIX C	
Photographs	
APPENDIX D	
Hydraulic Computations	
APPENDIX E	
Inventory Forms	



LAKE PARAN DAM
NORTH BENNINGTON, VERMONT

SECTION 5: HYDRAULIC/HYDROLOGIC

5.1 Evaluation of Features

a. Design Data

There was no existing design data available for the structures at Lake Paran.

b. Experience Data

Other than an account of the dam failing soon after construction in the 1850's, no other information with respect to lake levels was available.

c. Visual Observations

At the time of the inspection the outlet gate structure was completely silted up and inoperable. The gate had not been open since its installation. Efforts to open the gate subsequent to the inspection to lower the lake level resulted in partial removal of the gate and destruction of the operating mechanism. The downstream outlet of the emergency drawdown structure was severely eroded and could collapse, resulting in limited service or total disablement of the outlet.

d. Overtopping Potential

Preliminary computations indicate that the test flood (one half of the probable maximum flood) will overtop the embankment by 3.3 feet.

Downstream flooding as a result of breaching of the dam would result in a flood wave 16 to 20 feet high. This flood wave would endanger the area shown striped on the Drainage Area Delineation Map (Appendix D). The height of this wave is based on the assumption that the wave would be $\frac{2}{3}$ the dam height. Analysis by hydrographs was not possible due to the inadequacies of available mapping.

SECTION 4: OPERATIONAL PROCEDURES

4.1 Procedures

There are no operational procedures known.

4.2 Maintenance of Dam

The grass and brush are cut to provide operation of train traffic.

4.3 Maintenance of Operating Facilities

The gated outlet structure was the most obvious item which had no maintenance for years.

4.4 Description of any Warning System in Effect

There is no warning system associated with this facility.

4.5 Evaluation

Maintenance and operational procedures are nonexistent. As a result the wood gate had to be cut open with a chain saw, which was an emergency operation.

From just above White's Mill to it's mouth, Paran Creek flows through populated areas.

The downstream channel below the outlet works is completely overgrown and covered with fallen trees. It is an unlined channel.

The channel downstream of the spillway was free of obstructions, although many trees are growing on both sides and overhanging the channel.

3.2 Evaluation

The small dams on Paran Creek downstream of Lake Paran would increase the hazard of any overtopping or failure of the dam at Lake Paran. This would result in an increase in flood damages resulting solely from Lake Paran.

It was determined that there is danger of failure of this dam due to the presence of the major hole in the embankment on the upstream side. Therefore, it was recommended to the Corps of Engineers, on June 23, 1978, the morning after the inspection, that the lake be lowered immediately to a level below the top of the hole, or lower if necessary, to essentially eliminate seepage, and that subsequently an investigation be made to establish further needed actions. The condition of the hole was monitored on June 24 and 25, hourly, day and night, until representatives of North Bennington assumed the observations. The lake lowering was started on June 26, 1978 under the auspices of the Chairman of the Board of Trustees of North Bennington.

Any loss of storage due to sedimentation would have little effect on the surcharge height produced by the test flood, therefore this potential problem is of little concern in evaluation of dam overtopping.

The downstream channel area contains debris which may accumulate at road crossings downstream during flood stages, resulting in reduced flow-carrying capacities.

Based on these visual observations, it appears that the dam must, for practical purposes, be redesigned and rebuilt. It may be possible to incorporate part of the present embankment into the final dam. Specifically, the following items are significant:

- a. The seepage through the dam must be reduced and controlled.
- b. The outlet conduit must be rebuilt to repair locations where erosion has occurred and to preclude future erosion.
- c. The spillway discharge channel walls, and the soil behind them, must be redesigned to preclude the erosion and leakage that are occurring.

The trash rack was in relatively good condition.

The conduit leaving the gate was in good condition.

Directly leaving the gate structure was a 3' x 4-1/2' stone masonry conduit. There were no significant cracks observed and the alignment was good. At the point where there was a change in direction the conduit was continued as a 4-foot diameter corrugated metal pipe. This pipe may have a hole in it since an erosion gully has been formed above the pipe (see 3.1b).

The concrete headwall at the discharge end of the 4-foot diameter culvert has serious erosion problems, as the flow will drop vertically at the end of the concrete apron and then back under the structure (see photo #12). The flow has eroded a channel underground which exits approximately 15 feet downstream in the discharge channel.

d. Reservoir Area

The reservoir area consists of approximately 36 acres at the normal pool level. A considerable amount of aquatic growth and shoreline vegetation was visible around most of the lake with the worst being at the east end. Sedimentation has been a problem which had in the past been aggravated by a gravel operation on Paran Creek. A Vermont Fish and Game Department depth chart dated July 18, 1941 indicates a subaqueous channel on the east (left) end of the lake that had been 10 to 15 feet deep was now only 5 to 10 feet deep. In April of 1975 the Paran Recreation Department Incompany Cleanup Committee petitioned the State of Vermont Department of Water Resources to approve a dredging project. This was never carried out.

e. Downstream Channel

From the toe of the spillway for a distance of approximately 1/4 mile, the stream has a moderately steep gradient. The channel itself is free of vegetation, however, the overbanks are heavily vegetated with trees and dense brush which overhang the channel forming a canopy. The channel bottom contains cobbles and boulders.

Paran Creek enters a small 3-acre pond named White's Mill, 1/4 mile downstream from Lake Paran. From there Stark Mill Pond (3 acres), Cushman Pond (4 acres) and Polygraphic Pond (4 acres) are crossed before Paran Creek enters the Walloomsac River, approximately 1.5 miles below the Lake Paran Dam.

Photograph #7 is a view from left to right of the tracks. The slight downstream deflection of the track, approximately mid-point in the photograph, is located opposite the hole in the upstream face.

An erosion hole was found in the downstream face of the dam just over the top of the 4-foot diameter outlet conduit that is located at the right abutment. This hole was 2 feet wide along the dam, about 6 feet long, down slope, and at least four feet deep. The top of the hole is about 4 feet down slope from the downstream crest line.

Upon an inspection of the dam after drawdown another hole was found on the upstream face of the embankment (see photo #10).

Erosion holes were also found on both sides of the spillway discharge channel walls, upstream from the crest. These holes are up to 3 feet deep.

Additional zones of erosion were found on both sides of the outlet works discharge structure.

c. Appurtenant Structures

The general appearance of the concrete and stone masonry of the normal spillway is good. There were no cracks observed in the weir and the horizontal and vertical alignment were very good. One of the concrete walls which the weir ties into is cracked (see photo #4, Appendix C). The channel walls for the spillway discharge are comprised of a concrete section and a stone masonry section. Both sections are structurally sound. There are two substantial leaks in the masonry sections on the left abutment (see photo #3). There is a substantial hole on the right stone masonry abutment but no water was flowing during the time of inspection. The channel floor is composed of concrete just downstream of the spillway and hand placed marble blocks further downstream. The concrete was in good condition and not cracked. Also there was evidence of previous flow out of the interface between the downstream end of this wall and the abutting right embankment.

The general appearance of the concrete in the intake structure of the outlet works was very good. All aspects of the structure were examined. After the lake was lowered, a crack was observed in the wing wall of the gate structure (photo #12, Appendix C). There was no spalling of the concrete or obvious settlement of the structure. The slide or service gate was inspected but the equipment to test operation was not available. However, when the attempt was made to lower the lake, the gate was found to be inoperable.

SECTION 3: VISUAL INSPECTION

3.1 Findings

a. General

This dam is in imminent danger of failure when the reservoir is at normal level.

b. Dam

There is a major hole in the upstream face at a distance 265 feet right of the right wall of the spillway discharge channel. Figure 3 shows an estimated cross section of the dam at this location. The hole was visible just below the water surface on the day of inspection, June 22, 1978. The top of the hole was 7 feet in diameter and tapered down to about 3 feet in diameter at a depth of 7 to 10 feet, where it disappeared into the embankment. A fishline with a light weight on the end was dragged at least 25 feet into the hole by the current of water flowing into the hole.

Major outflow was occurring from the toe of the dam on the day of inspection. At that time heavy shrubs covered the entire downstream slope. Therefore paths were cut in a few locations to observe seepage from the toe. Approximately opposite the hole a major outflow was observed at the toeline of the dam and from a few feet up the face. The length of this zone of seepage was about 30 feet and thousands of gallons per minute were estimated to be flowing out. A portion of this flow is shown in photo #8. A second point of flow was found about midway between the spillway and the hole. The flow rate at this location was probably in the tens of gallons per minute. A third location of outflow was found about 100 feet to the right of the hole. Again tens of gallons per minute outflow was occurring from a zone near the toeline and two or three feet up the face. All flow was clear. It carried a few suspended particles but looked the same both upstream (in the lake) and downstream.

During a subsequent visit on June 25, 1978 a cloud of rusty water was placed in the hole upstream. In about 5-1/2 minutes, the rusty water was observed to exit from the downstream side. Based on the estimated flow velocity into the hole at the location where it was about 4 feet in diameter, and based on the volume of flow estimated in the stream at the toe of the dam, it appears that the flow into the hole was only one-half or two-thirds of the outflow. During our visit to the base of the dam on June 25, 1978, some cloudy water was seen, but it quickly cleared up.

SECTION 2: ENGINEERING DATA

2.1 Design

There are no documents available describing the design of this embankment. There are no existing plans on the spillway and no existing hydrological computations from a design phase. The gated outlet structure was reconstructed in 1956 because the previous structure was made of timbers and was rotting. These plans are available (see attached in Appendix B).

2.2 Construction

Refer to Section 1.2h for the construction history.

2.3 Operation

There are no known operational and maintenance procedures associated with Lake Paran Dam.

2.4 Evaluation

a. Availability

The plans for the embankment and the normal spillway are non-existent or unavailable. The plans for the new gate works appear to be adequate, available and were prepared by a registered professional engineer. These plans are stored in the office of the Chairman of the Board of Trustees, North Bennington.

b. Adequacy

The lack of indepth engineering data does not allow for a definitive review. Therefore the adequacy of this dam, structurally and hydraulically, can not be assessed from the standpoint of review of design calculations, but must be based primarily on the visual inspection, past performance history, and sound hydrologic and hydraulic engineering judgement.

c. Validity

Not applicable.

to the downstream face which has a 1:1 slope (see Figure 1). Elevation of the weir is 646.8 feet above mean sea level, which is 3.3 feet below the top of the dam.

At a point approximately 30 feet downstream from the weir, the spillway discharge channel constricts to form a 35-foot wide rectangular channel. The flow is confined to this width to approximately 63 feet downstream of the weir, at which point the flow expands into the natural stream channel. Marble blocks have been hand placed in the channel just downstream from the center of the embankment to form the discharge channel.

j. Regulating Outlets

The regulating outlet in the abutment at the right end of the dam consists of a gate 4' 4" x 6' 0" and a box conduit 5' 3" x 4' 0". The entrance invert is at an elevation of + 635.3 feet above mean sea level, 14.8 feet below the top of the dam (see photo #5 and Figure 2).

The conduit leading away from the gate is a stone masonry box culvert approximately 5' 3" x 4' 0" with a transition to 4' diameter corrugated metal pipe. There is a bend or change in direction at the transition in construction material. This pipe exits through a headwall on the downstream side of the embankment.

Subsequent to and as a result of the inspection on June 22, 1978 the outlet was opened, resulting in the destruction of the gate, gate stem, and operating mechanism. At that time it was not possible to open the gate, so a number of holes were punched through the gate with a battering ram and a portion of the gate was removed with a chain saw to lower the lake level.

g. Dam

(1) Type

According to verbal information provided by Mr. Bischoff of Vermont Railroads, the embankment is earth fill, composed of the local glacial till.

(2) Length

The overall length is 550 feet.

(3) Height

The maximum height is 29 feet.

(4) Top Width

The top width averages 23 feet.

(5) Side Slopes

Upstream - About 2.5H:1V
Downstream - About 1.4H:1V

(6) Zoning

None known.

(7) Impervious Core

None known.

(8) Cutoff

None known.

(9) Grout Curtain

None known.

(10) Other

According to Mr. Welling a row of timber piles exists just upstream of the railroad. This row was later buried.

i. Spillway

The spillway is an open concrete flume located near the left end of the dam. The overflow weir is approximately 90 feet long and is semihexagonal in plan. The weir has a vertical upstream face, is one foot wide at the top, and curved down

(2) Maximum Known Flood at Dam Site

No records of past flood discharges at the dam exist, however, the embankment reportedly washed out once within a year after construction, in the 1850's. The dam withstood the floods in November 1927, March 1936, and September 1938. However, the discharges from these storms at this site are not known.

(3) Spillway Capacity

With the pool at the top of dam, with zero freeboard, (approximately 650.1 feet m.s.l.) the spillway capacity is 1755 cfs. This result is based on the assumption that the Rutland Railroad bridge just downstream of the spillway does not become clogged with debris to control the discharge capacity. There is no trash rack or gate structure on the spillway.

c. Elevation Data

	<u>Elevation (assumed)</u> <u>(feet m.s.l.)</u>
Test Flood (1/2 PMF)	653.4
Top of Dam (Maximum)	651.9
Top of Dam (Minimum)	650.1
Recreation (Normal) Pool	647.0
Spillway Crest	646.8
Emergency Drawdown Upstream Invert	635.3
Streambed at Centerline of Dam	621.0

d. Reservoir Data

	<u>Feet</u>
Length of Pool at Top of Dam	3300 +
Length of Recreation (Normal) Pool	3300

e. Storage Data

	<u>Acre-Feet</u>
Test Flood (1/2 PMF)	464+
Top of Dam	345
Recreation (Normal) Pool	252

f. Reservoir Surface Area

	<u>Acres</u>
Test Flood (1/2 PMF)	36+
Top of Dam	36+
Recreation Pool	36
Spillway Crest	36

tory was obtained. Easement rights for the railroad were secured in 1851 and construction of the embankment was completed in 1855 or before, using glacial till. Reportedly some of the fill was placed during the winter using frozen soils. Within one year after construction the embankment was washed out, flooding North Bennington, and killing one person. Shortly thereafter the embankment was rebuilt.

In the early 1900's a spillway was constructed to form Lake Paran. Just prior to 1955 the spillway was reported to be composed of "timber planking containing a fill of loose stone." (See Report on Five Dams on Paran Creek, Appendix B.) In 1955 this old spillway was replaced with the existing concrete spillway.

Prior to 1955 there existed an old timber and concrete gate structure at the right (west) end of the embankment. The timbers were rotted at that time and in 1956 this gate was replaced with the existing structure.

1. Normal Operational Procedures

Normal operational procedures are not known. The gate at the right end of the embankment was not operable at the time of inspection.

1.3 Pertinent Data

a. Drainage Area

The drainage area above the dam consists of 15.6 square miles of rolling to mountainous terrain, with a maximum relief of 1,389 feet. The primary water course supplying Lake Paran is Paran Creek.

Soils within the drainage area range from the well-drained soils formed in glacial tills on limestone and slate uplands to soils formed in the sandy and gravelly fluvial deposits and the poorly-drained silty glacial-lacustrine deposits.

b. Discharge at Dam Site

(1) Outlet Works

Outlet works at Lake Paran consist of two structures, the spillway, described below, and a gated emergency drawdown structure on the right end of the dam. The emergency drawdown structure opens into a gated 4' x 5-1/2' box culvert with an invert elevation of ± 653.3 feet m.s.l., which is about 11.5 feet below the spillway crest. Downstream of the box culvert is a 4-foot diameter corrugated metal pipe outlet conduit.

c. Size Classification

The size classification of Lake Paran Dam would place it in the category of small. The height of the earth embankment is a maximum of 28-30 feet. The storage capacity with the lake level at the spillway crest (normal level) is 252 acre-feet; with the lake at top of dam the storage is approximately 350 acre-feet.

d. Hazard Classification

The potential for hazard in the event of failure of this dam is classified as high. It has been reported that the dam did fail in the 1850's. Many of the homes and mills along Paran Creek were destroyed and the death of a child resulted. Today approximately 25% of the Village of North Bennington is along this portion of Paran Creek. Most of the residential population and several industries would be endangered in the event of failure of this dam.

e. Ownership

Lake Paran is owned and operated by Paran Recreation, Inc., North Bennington, Vermont.

The railroad right-of-way has been turned over to the State of Vermont.

The ownership of the embankment itself is not known.

f. Operation

Lake Paran has no one individual responsible for the day to day operation of the dam or for periodic maintenance. The individual contacted to obtain Right of Entry was Mr. George Elwell, President, Paran Recreation, Inc., North Bennington, Vermont. Phone 802-447-7450.

g. Purpose of Dam

The impoundment is used for recreational purposes. Amenities provided by Paran Recreation, Inc. include the beach, a raft, public toilets, parking, lifeguards, etc. The embankment is used as a railroad right-of-way.

h. Design and Construction History

Based on verbal history obtained from Mr. Fred Welling, Chairman of the Board of Trustees, North Bennington, and Mr. George Bischoff of Vermont Railroads, the following construction his-

NATIONAL DAM INSPECTION PROGRAM
PHASE I INSPECTION REPORT
LAKE PARAN

SECTION 1: PROJECT INFORMATION

1.1 General

a. Authority

Authorization for the project was derived from The Dam Inspection Act, Public Law 92-367 which authorized the Secretary of the Army through the Corps of Engineers to initiate a program of safety inspection of dams throughout the United States. The work was performed under Contract No. DACW 33-78-C-0341 between the New England Division, Corps of Engineers and Dufresne-Henry Engineering Corporation, North Springfield, Vermont.

b. Purpose

The purpose of this inspection is to evaluate Lake Paran Dam and its appurtenant structures and to identify any conditons which jeopardize public safety.

This project will encourage and prepare the states to initiate effective dam safety programs. The project also provides for the verification and updating of the National Inventory of Dams.

1.2 Description of Project

a. Location

Lake Paran Dam is located on Paran Creek in the Hudson River Basin in the Village of North Bennington, Bennington County in southwestern Vermont. The site is located approximately 1500 feet upstream from the Village of North Bennington and 1.7 miles from the confluence of Paran Creek and the Walloomsac River.

b. Description of Dam and Appurtenances

The embankment is 550 feet long and 29 feet high above the stream bed. The upstream slope is about 2.5H:1V and the downstream slope is about 1.4H:1V. At the left end is a 90-foot long uncontrolled concrete spillway with a crest level about 3.3 feet below the top of the dam. At the right end there is a gate, with a 4-foot diameter outlet pipe, with the invert about 11.5 feet below the spillway crest and 14.8 feet below the top of the dam. At the left end of the embankment there is a railroad bridge over the spillway discharge channel.

SECTION 6: STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability

a. Visual Observations

Based on visual observations, this dam is in imminent danger of failing by internal erosion and subsequent collapse. There were no observations made that would indicate instability in the form of downstream sliding, slope failure or cracking.

b. Design and Construction Data

There are no such data available on which to base an evaluation of structural stability.

c. Operating Records

Operating records are nonexistent.

d. Post-construction Changes

See Section 1.2h.

e. Seismic Stability

The dam is in Seismic Zone 2, therefore no seismic analysis is required by the USCE Guidelines.

SECTION 7: ASSESSMENT, RECOMMENDATIONS/ REMEDIAL MEASURES

7.1 Dam Assessment

a. Condition

This dam is in danger of failing if the lake is maintained at normal levels. Preliminary computations indicate a severe overtopping potential of the dam embankment. In the event of a test flood (1/2 PMF) a surcharge height of 3.3 feet above the top of the embankment would occur. The discharge from Lake Paran caused by either the test flood or failure of the dam is of greatest concern with respect to the other small dams downstream. Even in the event that Lake Paran did not fail during the test flood the discharge would severely endanger the small dams downstream. Failure of Lake Paran Dam would produce a flood wave 16 to 20 feet high.

Even though calculations are of a preliminary nature and accumulated information is limited, it becomes obvious that the spillway capacity does not meet the screening criteria set forth by the Corps of Engineers, and that a significant overtopping potential exists.

b. Adequacy of Information

The available information is not adequate to evaluate the stability of the dam against horizontal sliding, slope stability or cracking. In view of the large hole in the upstream face, failure by internal erosion is an immediate probability. However, since the character of the embankment itself is not known, one cannot judge how extensive a repair is needed to remove the danger of failure by internal erosion.

c. Urgency

The need was immediate to maintain a lake level low enough to essentially eliminate flow through the dam. Therefore, the recommendation was provided to the Corps of Engineers immediately.

d. Necessity for Additional Investigations

If it is desired to use this dam at normal lake levels, it must be redesigned and rebuilt.

7.2 Recommendations

The owner must engage an engineer to redesign and prepare contract drawings for reconstruction if the embankment is to be used as a dam.

Immediate consideration should be given to providing a means of increased spillway capacity. This is necessary due to the limited discharge capacity of the existing structure. The reservoir does not have sufficient storage to contain even a minor event without building a pool higher than the sink holes.

7.3 Remedial Measures

a. Alternatives

- (1) To decrease the overtopping potential the following should be considered:
 - i. Significantly increase weir capacity to 1/2 PMF capacity.
 - ii. Provide adequate emergency drawdown structures.
 - iii. Provision to guarantee that flow through any bridge structure will not constrict flow.
- (2) The dam may be abandoned if the lake is drained completely.

b. Operation and Maintenance Procedures

Due to the location of the dam upstream of a populated area, and the limited discharge capacity of the outlet works, round the clock surveillance should be provided during periods of unusually heavy precipitation. In addition the owner should develop a formal warning procedure with local officials for alerting downstream residents in case of emergency.

APPENDIX A
VISUAL INSPECTION CHECKLIST

VISUAL INSPECTION CHECK LIST
PARTY ORGANIZATIONPROJECT Lake Paran DamDATE June 22, 1978TIME 11:00WEATHER Mostly sunny, humid,
4-10 mph wind

W.S. ELEV. _____ U.S. _____ DN.S. _____

PARTY:

- | | |
|-----------------------------------|-----------|
| 1. <u>Walter Henry, D&H</u> | 6. _____ |
| 2. <u>Michael Peloso, D&H</u> | 7. _____ |
| 3. <u>Eric Slavin, D&H</u> | 8. _____ |
| 4. <u>Steve Poulos, GEI</u> | 9. _____ |
| 5. _____ | 10. _____ |

PROJECT FEATURE	INSPECTED BY	REMARKS
1. _____	_____	_____
2. _____	_____	_____
3. _____	_____	_____
4. _____	_____	_____
5. _____	_____	_____
6. _____	_____	_____
7. _____	_____	_____
8. _____	_____	_____
9. _____	_____	_____
10. _____	_____	_____

PERIODIC INSPECTION CHECK LIST

2 of 10

PROJECT LAKE PARAN DAM DATE June 22, 1978
 PROJECT FEATURE _____ NAME _____
 DISCIPLINE Geotechnical NAME S. J. Poulos

AREA EVALUATED	CONDITION
<u>DAM EMBANKMENT</u>	
Crest Elevation	650.1 MSL
Current Pool Elevation	647.0 MSL
Maximum Impoundment to Date	650.1 MSL
Surface Cracks	None observed.
Pavement Condition	Railroad on crest. Apparently used by trains 8-10 times/week.
Movement or Settlement of Crest	None observed.
Lateral Movement	About 218 ft. rt. of rt. spillway wall the tracks are displaced ds slightly (~2 in.
Vertical Alignment	No vertical misalignment observed.
Horizontal Alignment	See "Lateral Movement"
Conditions at Abutment and at Concrete Structures	Considerable erosion around and below 4' diameter outlet structure. At upstream end, no erosion or misalignment observed.
Indications of Movement of Structural Items on Slopes	Sink holes due to erosion on left and right sides of spillway training walls, on u.s. side of embankment. 2 ft. diameter drain culvert above outlet structure, is in complete disrepair.
Trespassing on Slopes	Free access. Ties, strapping and miscellaneous trash dumped on d.s. slope.
Sloughing or Erosion of Slopes or Abutments	15 ft. to rt. of outlet structure there is a 3 to 4 ft. deep sinkhole directly over the 4 ft. dia. outlet pipe, just d.s. of d.s. crest line. A 6 ft. dia. hole exists about 265 ft. right of rt. wall of spillway. Decreases in dia. and accepts a fish line 25' long. Flow rate in 1000's gpm into hole. Whirlpool forms intermittently.
Rock Slope Protection - Riprap Failure	Riprap at water surface is discontinuous and slightly wave cut.
Unusual Movement or Cracking at or Near Toes	None observed.
Unusual Embankment or Downstream Seepage	100's or 1000's of gpm exiting from d.s. toe up to 2' above toe. Water was clear. Flow occurs at about 3 zones along toe 10 to 30 ft. long each.

PERIODIC INSPECTION CHECK LIST

3 of 10

PROJECT LAKE PARAN DAM

DATE June 22, 1978

PROJECT FEATURE _____

NAME _____

DISCIPLINE Geotechnical

NAME S. J. Poulos

AREA EVALUATED	CONDITION
<u>DAM EMBANKMENT</u>	
Piping or Boils	None observed.
Foundation Drainage Features	None apparent.
Toe Drains	None.
Instrumentation System	None.
Vegetation	Covered with trees and shrubs on d.s. slope.

PERIODIC INSPECTION CHECK LIST

4 of 10

PROJECT LAKE PARAN DAM DATE June 22, 1978
 PROJECT FEATURE _____ NAME _____
 DISCIPLINE Geotechnical NAME S. J. Poulos

AREA EVALUATED	CONDITION
<u>DIKE EMBANKMENT</u>	
Crest Elevation	No dikes.
Current Pool Elevation	
Maximum Impoundment to Date	
Surface Cracks	
Pavement Condition	
Movement or Settlement of Crest	
Lateral Movement	
Vertical Alignment	
Horizontal Alignment	
Condition at Abutment and at Concrete Structures	
Indications of Movement of Structural Items on Slopes	
Trespassing on Slopes	
Sloughing or Erosion of Slopes or Abutments	
Rock Slope Protection - Riprap Failures	
Unusual Movement or Cracking at or near Toes	
Unusual Embankment or Downstream Seepage	
Piping or Boils	
Foundation Drainage Features	
Toe Drains	
Instrumentation System	

PERIODIC INSPECTION CHECK LIST

5 of 10

PROJECT LAKE PARAN

DATE June 22, 1978

PROJECT FEATURE _____

NAME _____

DISCIPLINE Geotechnical

NAME Poulos

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - INTAKE CHANNEL AND INTAKE STRUCTURE</u>	
a. Approach Channel	
Slope Conditions	Channel to outlet works almost completely filled in with lake bottom silt. A small V-notch channel exists through silt to gate, with max. depth 4 ft. below water surface. Weeds growing within.
Bottom Conditions	
Rock Slides or Falls	None.
Log Boom	None.
Debris	See above.
Condition of Concrete Lining	Horizontal crack in right abutment wall and misalignment.
Drains or Weep Holes	Not observable.
b. Intake Structure	
Condition of Concrete	Good
Stop Logs and Slots	Not applicable.

PERIODIC INSPECTION CHECK LIST

6 of 10

PROJECT LAKE PARAN DAM

DATE June 22, 1978

PROJECT FEATURE _____

NAME M. R. Peloso

DISCIPLINE Geotechnical

NAME S. J. Poulos

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - CONTROL TOWER</u>	
a. Concrete and Structural	
General Condition	Good
Condition of Joints	Good
Spalling	None observed.
Visible Reinforcing	None observed.
Rusting or Staining of Concrete	None
Any Seepage or Efflorescence	None
Joint Alignment	Good
Unusual Seepage or Leaks in Gate Chamber	Some seepage visible. Less than 1 gpm.
Cracks	Some minor cracks at joints.
Rusting or Corrosion of Steel	Some rusting of cog and gear wheel.
b. Mechanical and Electrical	
Air Vents	None
Float Wells	None
Crane Hoist	None
Elevator	None
Hydraulic System	None
Service Gates	Inoperable
Emergency Gates	None
Lightning Protection System	None
Emergency Power System	None
Wiring and Lighting System	None

PERIODIC INSPECTION CHECK LIST

7 or 10

PROJECT LAKE PARAN DAM

DATE June 22, 1978

PROJECT FEATURE _____

NAME _____

DISCIPLINE Geotechnical

NAME S. J. Poulos

AREA EVALUATED	CONDITION
<p><u>OUTLET WORKS - TRANSITION</u> <u>AND CONDUIT</u></p> <p>General Condition of Concrete</p> <p>Rust or Staining on Concrete</p> <p>Spalling</p> <p>Erosion or Cavitation</p> <p>Cracking</p> <p>Alignment of Monoliths</p> <p>Alignment of Joints</p> <p>Numbering of Monoliths</p>	
	None apparent.
	None observed.
	None observed.
	None observed.
	Not applicable.
	Not applicable.
	Not applicable.
	Note:
	Conduit is of stone masonry construction and alignment and condition appears to be very good.
	Conduit changes direction and a 48" diameter C.M.P. is used to cross under the railroad embankment.

PERIODIC INSPECTION CHECK LIST

8 of 10

PROJECT LAKE PARAN DAM

DATE June 22, 1978

PROJECT FEATURE _____

NAME Peloso

DISCIPLINE Geotechnical

NAME S. J. Poulos

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - OUTLET STRUCTURE AND OUTLET CHANNEL</u>	
General Condition of Concrete	Walls are fair; apron is poor.
Rust or Staining	None.
Spalling	Serious spalling
Erosion or Cavitation	And erosion on concrete apron.
Visible Reinforcing	None
Any Seepage or Efflorescence	None
Condition at Joints	Not observed.
Drain Holes	None observed.
Channel	
Loose Rock or Trees Overhanging Channel	Completely cluttered with trees and broken portions of structure. Channel slopes are eroded.
Condition of Discharge Channel	Poor
	Note: Serious erosion at apron where discharging water drops vertically and flows underground 15' before it exits to the channel.

PERIODIC INSPECTION CHECK LIST

9 of 10

PROJECT LAKE PARAN DAMDATE June 22, 1978

PROJECT FEATURE _____

NAME M. R. PelosoDISCIPLINE GeotechnicalNAME S. J. Poulos

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u>	
a. Approach Channel	
General Condition	Not observable, underwater.
Loose Rock Overhanging Channel	None
Trees Overhanging Channel	None
Floor or Approach Channel	Not observable, underwater.
b. Weir and Training Walls	
General Condition of Concrete	Good
Rust or Staining	None
Spalling	None
Any Visible Reinforcing	None
Any Seepage or Efflorescence	Several seeps from walls of training walls downstream of weir, one flowing.
Drain Holes	None evident.
c. Discharge Channel	
General Condition	Fair
Loose Rock Overhanging Channel	Some loose stones in walls may become dislodged.
Trees Overhanging Channel	Much shrubbery and trees up to 2 feet size.
Floor of Channel	Good condition.
Other Obstructions	A few railroad ties lie in channel

PERIODIC INSPECTION CHECK LIST

10 of 10

PROJECT LAKE PARAN DAMDATE June 22, 1978

PROJECT FEATURE _____

NAME _____

DISCIPLINE GeotechnicalNAME S. J. Poulos

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - SERVICE BRIDGE</u>	Not Applicable
a. Super Structure	Note: Railroad bridge crosses the channel.
Bearings	Training walls of channel are abutments for bridge
Anchor Bolts	
Bridge Seat	
Longitudinal Members	
Under Side of Deck	
Secondary Bracing	
Deck	
Drainage System	
Railings	
Expansion Joints	
Paint	
b. Abutment & Piers	
General Condition of Concrete	
Alignment of Abutment	
Approach to Bridge	
Condition of Seat & Backwall	





FIGURE 2

DUFRESNE-HENRY ENGINEERING CORP. ARCHITECT-ENGINEER		U.S. ARMY ENGINEER DIV. NEW ENGLAND CORPS OF ENGINEERS WALTHAM, MASS.	
NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS			
LAKE PARAN DAM			
NORTH BENNINGTON		(2) VERMONT	
C.A.	22-0551	SCALE	JULY 1978
		DATE	




VIEW OF OUTLET STRUCTURE FROM RAILROAD EMBANKMENT



INDICATION OF DEBRIS BUILD UP IN FRONT OF TRASH RACK AT OUTLET STRUCTURE

LAKE PARAN







FIGURE 1



DUFRESNE-HENRY ENGINEERING CORP. ARCHITECT-ENGINEER		U.S. ARMY ENGINEER DIV. NEW ENGLAND CORPS OF ENGINEERS WALTHAM, MASS.	
NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS			
LAKE PARAN DAM			
NORTH BENNINGTON		VERMONT	
C.N.	22-0551	SCALE	DATE



VIEW OF SPILLWAY FROM THE LEFT TRAINING WALL



DISCHARGE CHANNEL LOOKING UPSTREAM



Scale: 1"=2'



LAKE PARAN

On Dec. 8, 1955 the undersigned visited Lake Paran to view the new construction on the spillway and the outlet gate. Mr. Welling, the Treasurer at the Stark Paper Co., who owns the dam, was also along on the visit.

The new construction on the spillway section is practically complete. The spillway section of the dam is made up of timber planking over stone fill. The planking and timbers were old and rotting so that water was leaking thru it. The old timber and loose rocks have been removed and replaced with concrete. The overflow crest is 90 feet long and is built in a semi hexagon fashion. The upstream face is vertical, a crest width of 1 foot and a downstream slope of approx. 45° . This then leads to a chute some 4 feet lower than the crest. The chute is some 40 feet wide leading to a bridge under the railroad. The railroad fill makes up the rest of the dam. It is approx. 4 feet higher than the crest of the spillway.

At the West side of the fill is an old gate structure. It was built of timber and concrete, but the timbers are all rotted away. Mr. Welling plans on constructing a new gate structure as soon as he has finished the spillway.

Lake Paran has a drainage area of 15 square miles and flows 36 acres. The reservoir is presently used for recreation. The construction at the dam appears very good and should last for a great many years.

Mr. Welling will send us a sketch of the gate structure as soon as they decide what should be put in for the new structure.

JOHN E. CERUTTI
WATER CONSERVATION BOARD
Dec. 8, 1955

INSPECTION REPORT
ON
Lake Paran Dam

1. Date of inspection 4/10/52 2. Water conditions overflowing pond

GENERAL DATA:


3. Location of dam Paran Cr., N. Bennington.
4. Owner and operator _____
5. Characteristic features of dam embankment supporting a
railroad, timber-lined chute spillway
6. Other related data (see writer's previous report)

OBSERVATIONS:

7. Condition of structure Embankment - perceptible seepage
at toe along east half - fill remains stable;
Spillway - some of the rotted timber planking have
been removed by action of water;
Sluiceway - crowded with debris.
8. Condition of equipment none
9. Operation none
10. Maintenance embankment weed growth under
control common with RR right of way.

REMARKS:

Inspected by JHH




Steel Steel & Rein. Steel
 details to be checked
 by Supplier.

O. B. Rankin P. Eng. 9111
 Jan 16/56

(2)


Gate Detail Lake Poron	
TOWN OF Bennington Vt	
ROAD NO. _____	BRIDGE NO. _____
William E. Dooley	
No. Bennington Vt	
SCALE 1/2" = 1'-0"	
SURVEYED BY _____	CHECKED BY _____
PROJECT NO. _____	
SHEET 2 OF 2	




Base Plan



Half Plan of Gate




Gate




Half Section DD


Re 14# 20 Reg'd
 A7 14# 20 Reg'd
 A8 14# 20 Reg'd
 A9 14# 20 Reg'd
 A10 14# 20 Reg'd
 A11 14# 20 Reg'd
 A12 14# 20 Reg'd
 A13 14# 20 Reg'd
 A14 14# 20 Reg'd
 A15 14# 20 Reg'd
 A16 14# 20 Reg'd
 A17 14# 20 Reg'd
 A18 14# 20 Reg'd
 A19 14# 20 Reg'd
 A20 14# 20 Reg'd
 A21 14# 20 Reg'd
 A22 14# 20 Reg'd
 A23 14# 20 Reg'd
 A24 14# 20 Reg'd
 A25 14# 20 Reg'd
 A26 14# 20 Reg'd
 A27 14# 20 Reg'd
 A28 14# 20 Reg'd
 A29 14# 20 Reg'd
 A30 14# 20 Reg'd
 A31 14# 20 Reg'd
 A32 14# 20 Reg'd
 A33 14# 20 Reg'd
 A34 14# 20 Reg'd
 A35 14# 20 Reg'd
 A36 14# 20 Reg'd
 A37 14# 20 Reg'd
 A38 14# 20 Reg'd
 A39 14# 20 Reg'd
 A40 14# 20 Reg'd
 A41 14# 20 Reg'd
 A42 14# 20 Reg'd
 A43 14# 20 Reg'd
 A44 14# 20 Reg'd
 A45 14# 20 Reg'd
 A46 14# 20 Reg'd
 A47 14# 20 Reg'd
 A48 14# 20 Reg'd
 A49 14# 20 Reg'd
 A50 14# 20 Reg'd
 A51 14# 20 Reg'd
 A52 14# 20 Reg'd
 A53 14# 20 Reg'd
 A54 14# 20 Reg'd
 A55 14# 20 Reg'd
 A56 14# 20 Reg'd
 A57 14# 20 Reg'd
 A58 14# 20 Reg'd
 A59 14# 20 Reg'd
 A60 14# 20 Reg'd
 A61 14# 20 Reg'd
 A62 14# 20 Reg'd
 A63 14# 20 Reg'd
 A64 14# 20 Reg'd
 A65 14# 20 Reg'd
 A66 14# 20 Reg'd
 A67 14# 20 Reg'd
 A68 14# 20 Reg'd
 A69 14# 20 Reg'd
 A70 14# 20 Reg'd
 A71 14# 20 Reg'd
 A72 14# 20 Reg'd
 A73 14# 20 Reg'd
 A74 14# 20 Reg'd
 A75 14# 20 Reg'd
 A76 14# 20 Reg'd
 A77 14# 20 Reg'd
 A78 14# 20 Reg'd
 A79 14# 20 Reg'd
 A80 14# 20 Reg'd
 A81 14# 20 Reg'd
 A82 14# 20 Reg'd
 A83 14# 20 Reg'd
 A84 14# 20 Reg'd
 A85 14# 20 Reg'd
 A86 14# 20 Reg'd
 A87 14# 20 Reg'd
 A88 14# 20 Reg'd
 A89 14# 20 Reg'd
 A90 14# 20 Reg'd
 A91 14# 20 Reg'd
 A92 14# 20 Reg'd
 A93 14# 20 Reg'd
 A94 14# 20 Reg'd
 A95 14# 20 Reg'd
 A96 14# 20 Reg'd
 A97 14# 20 Reg'd
 A98 14# 20 Reg'd
 A99 14# 20 Reg'd
 A100 14# 20 Reg'd






Section FF



Section EE







Trash Rack



Side section of Present on d

Scale 3/4" = 1'-0"



At the west end is an outlet structure, formerly used for regulated discharge from the lake. It now exists with old abandoned timber intake works and gate, and a 4 foot diameter corrugated metal culvert through the embankment.

Remarks - Since the dam is no longer used for the purpose originally intended, it has been left with no maintenance except for what is secondary from the upkeep given to the railroad right-of-way along the embankment.

The timbers in both the spillway and the outlet structure are in bad decay. As a result, excessive leakage occurs, particularly so in the spillway section where it passes through the stone fill under the planking. However, this leakage is where it cannot do serious harm to the embankment. The concrete and masonry portions of these outlet structures and the metal culvert pipe are in good condition.

Some water was noticed in the ditch at the downstream toe of the dam. This could be seepage through the embankment or it could be area drainage or both. From casual observation the embankment appeared in a stable condition. Ample section for stability is indicated.

Concluding - Lake Paran dam is the most important of this group of dams. Properly manipulated, it can serve as a flood control structure because of its storage potential which may reduce the flood peak in Paran Creek between 40 and 50 percent.

The timber portion of the spillway should be repaired, preferably replaced with a more water-tight section. For the conduit at the west end of the dam, improvements should be such as to provide free discharge at the higher pond levels and thus augment the spillway which can just about handle a flood of past record size.

Lake Paran Dam

Layout - Lake Paran is created by a high earth embankment which also serves as the right-of-way for the Bennington Branch of the Rutland Railroad. This embankment (about 500 feet long) has an average top width of 23 feet and a maximum depth between 25 and 30 feet. Its downstream upstream slope about 1 on 2 or flatter. The face has a slope of about 1 on 1 and its upstream face has a sparse cover of large boulders while the downstream face is overgrown with wild grass.

At the east end of the embankment is a spillway chute. The overflow crest for this chute is shown in Figure 1. This crest, built in a semi-hexagon fashion, has a total length of about 75 feet and is 4 feet below the top of the dam. Its section is made up of timber planking containing a fill of loose stone. It has a crest width of 1 foot, a vertical upstream face, and a sloping downstream face of about 45° . The chute is a sloped rectangular channel, 35 feet wide, beginning about 4 feet lower in elevation than the crest. It has concrete sides, and a bottom of timber planks in the upper portions and hand-placed stone in the lower portions. A steel girder bridge over the channel provides for the railroad crossing.




Fig. 1 Timber portion of chute spillway, Lake Paran dam

BENNINGTON
WALTER B. RENFREW
NEWSBURY
ANCIS W. LEACH
RUPERT



STATE OF VERMONT
WATER CONSERVATION BOARD
MONTPELIER

REPORT ON FIVE DAMS ON PARAN CREEK

IN
BENNINGTON, VERMONT

The only dams of jurisdictional size in the town of Bennington are the five dams located on Paran Creek in the vicinity of the village of North Bennington. These were examined by the writer last July and their condition noted herein.


Summary of Pertinent data

Qualifying data on each dam is given below in the order of its location in the course of the stream.

<u>Designation</u>	<u>Owner of dam</u>	<u>Present use of dam</u>	<u>Size of Pond</u>		<u>Drainage Area in sq. mi.</u>
			<u>Surface area in acres</u>	<u>volume in cu. ft.</u>	
Lake Paran	Stark Paper Co. & Rutland R.R.	Recreation	36	11,000,000	15
White's Mill	Ed White	(not in use)	3	500,000	15
Stark Mill	Stark Paper Co. (D. Welling) owner	(not in use)	2	500,000	15
Cushman	H.D. Cushman Mfg. Co.	Augments a steam plant in private power generation	4	800,000	16
Polygraphic	Polygraphic Co. of America	Minor use for water supply for fire protection	4	500,000	17

APPENDIX B

1. Data is unavailable pertaining to design, construction and maintenance.
2. Copies of past inspection reports.
3. Plans showing layout of dam sections details of various features.



ESTIMATED CROSS SECTION

1"=25' APPROX.

CONSTRUCTED 1852

CLIENT NO	22-0551	DUFRESNE-HENRY ENGINEERING CORP.		FIGURE 3
ENGINEER	MRP			
DRAWN BY	RB	LAKE PARAN DAM		A
DATE	6-25-78			
		NORTH BENNINGTON		
		VERMONT		

LEFT

660

655

650

645

640

635

0,650.1


46,650.1

64,650.1

160,650.1

218,650.1

288,650.3







FIGURE 4


DUFRESNE-HENRY ENGINEERING CORP. ARCHITECT-ENGINEER		U.S. ARMY ENGINEER DIV. NEW ENGLAND CORPS OF ENGINEERS WALTON, MASS.	
NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS			
LAKE PARAN DAM TOP OF DAM PROFILE			
NORTH DENNINGTON		VERMONT	
DRAWN	RR	SCALE	1"=20' HOR. AND VERT.
ENGR	MRP	DATE	JULY 19, 1978

APPENDIX C

PHOTOGRAPHS

1. Upstream face of dam, looking west from spillway.
2. Downstream face of dam, looking west from railroad bridge.
3. Leakage in stone masonry right abutment/training wall, 2 feet from end of concrete wall.
4. Crack in right abutment of spillway training wall.
5. Outlet structure at west end of impoundment.
6. Outlet tube 4' diameter which passed below railroad embankment.
7. Looking west from railroad bridge, track alignment is offset at location of sinkhole.
8. The volume of flow indicated in this photograph is typical of a 30' long section at the toe of slope.
9. Upstream face of dam, looking west from spillway, sinkhole was located at mound of gravel.
10. Approximately 100' west of the large sinkhole another was starting to form.
11. Outlet structure at west end of dam, a portion of the debris removed can be seen in the upper left hand corner.
12. Crack in right abutment wall of outlet structure, wall has a vertical misalignment of 2".
13. Reduction of flow as a result of filling the sink hole with cobbles and gravel.
14. Flow has completely stopped in this section as a result of lowering the pool 4'.





P A R A N

EMERGENCY SPILLWAY

7" DIAMETER
SINK HOLE

RAILROAD
BRIDGE

FIGURE
5

DUFRESNE-HENRY ENGINEERING CORP.
ARCHITECT-ENGINEER

U.S. ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASS.

NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS

LOCATIONS OF PHOTOGRAPHS
TAKEN 6/22, 6/26 & 7/3/1978

NO. BENNINGTON

VERMONT

22-6551

ENG.

MP

SCALE
DATE



#1 UPSTREAM FACE OF DAM LOOKING WEST FROM SPILLWAY




#2 DOWNSTREAM FACE OF DAM LOOKING WEST FROM RAILROAD BRIDGE




#3

LEAKAGE IN STONE MASONRY RIGHT ABUTMENT/TRAINING WALL,
2 FEET FROM END OF CONCRETE WALL



#4

CRACK IN RIGHT ABUTMENT OF
SPILLWAY TRAINING WALL



#5 OUTLET STRUCTURE AT WEST END OF IMPOUNDMENT



#6 OUTLET TUBE 4' DIAMETER WHICH PASSED BELOW RAILROAD EMBANKMENT



#7

LOOKING WEST FROM RAILROAD BRIDGE TRACK ALIGNMENT
IS OFFSET AT LOCATION OF SINK HOLE.




#8

THE VOLUME OF FLOW INDICATED IN THE PHOTOGRAPH IS
TYPICAL OF A 30' LONG SECTION AT THE TOE OF SLOPE.

PHOTOGRAPHS OF LAKE PARAN AFTER POOL WAS LOWERED
4' JULY 3, 1978.



#9 UPSTREAM FACE OF DAM LOOKING WEST FROM SPILLWAY, SINK
HOLE WAS LOCATED AT MOUND OF GRAVEL



#10

APPROXIMATELY 100' WEST
OF THE LARGE SINK HOLE
ANOTHER WAS STARTING TO
FORM.



#11 OUTLET STRUCTURE AT WEST END OF DAM, A PORTION OF THE DEBRIS REMOVED CAN BE SEEN IN THE UPPER LEFT HAND CORNER.



#12 CRACK IN RIGHT ABUTMENT WALL OF OUTLET STRUCTURE, WALL HAS A VERTICAL MISALIGNMENT OF 2".



#13 REDUCTION OF FLOW AS A RESULT OF FILLING THE SINK HOLE WITH
COBBLES AND GRAVEL



#14 FLOW HAS COMPLETELY STOPPED IN THIS SECTION AS A RESULT
OF LOWERING THE POOL 4'.

APPENDIX D
HYDRAULIC COMPUTATIONS

1. Hydrologic Computations.
2. Outline of drainage area and affected downstream areas.

STATION 1 1

INFORMATION OUTLAYS AND OBSERVED FLOORS											
0.	4000.	8000.	12000.	16000.	20000.	24000.	28000.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	3.	PRECIPITATION AND EACH	
									2.	1.	

[illegible]

3 22 60	0.00	0.00	174.
3 23 30	0.00	0.00	171.
3 23 60	0.00	0.00	169.

SUM	20.60	15.74	338228.
-----	-------	-------	---------

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	25292.	19100.	6664.	2349.	338229.
INCHES		11.39	15.90	16.81	16.81
AC-FY		9476.	13226.	13984.	13984.

2 13 00	0.75	0.00
2 14 30	1.17	1.09
2 14 60	1.17	1.09
2 15 30	2.95	2.88
2 15 60	2.95	2.88
2 16 30	1.09	1.01
2 16 60	1.09	1.01
2 17 30	0.86	0.78
2 17 60	0.86	0.78
2 18 30	0.08	0.01
2 18 60	0.08	0.01
2 19 30	0.08	0.01
2 19 60	0.08	0.01
2 20 30	0.08	0.01
2 20 60	0.08	0.01
2 21 30	0.08	0.01
2 21 60	0.08	0.01
2 22 30	0.08	0.01
2 22 60	0.08	0.01
2 23 30	0.08	0.01
2 23 60	0.08	0.01
3 0 30	0.00	0.00
3 0 60	0.00	0.00
3 1 30	0.00	0.00
3 1 60	0.00	0.00
3 2 30	0.00	0.00
3 2 60	0.00	0.00
3 3 30	0.00	0.00
3 3 60	0.00	0.00
3 4 30	0.00	0.00
3 4 60	0.00	0.00
3 5 30	0.00	0.00
3 5 60	0.00	0.00
3 6 30	0.00	0.00
3 6 60	0.00	0.00
3 7 30	0.00	0.00
3 7 60	0.00	0.00
3 8 30	0.00	0.00
3 8 60	0.00	0.00
3 9 30	0.00	0.00
3 9 60	0.00	0.00
3 10 30	0.00	0.00
3 10 60	0.00	0.00
3 11 30	0.00	0.00
3 11 60	0.00	0.00
3 12 30	0.02	0.00
3 12 60	0.02	0.00
3 13 30	0.03	0.00
3 13 60	0.03	0.00
3 14 30	0.04	0.00
3 14 60	0.04	0.00
3 15 30	0.09	0.02
3 15 60	0.09	0.02
3 16 30	0.03	0.00
3 16 60	0.03	0.00
3 17 30	0.03	0.00
3 17 60	0.03	0.00
3 18 30	0.00	0.00
3 18 60	0.00	0.00
3 19 30	0.00	0.00
3 19 60	0.00	0.00
3 20 30	0.00	0.00
3 20 60	0.00	0.00
3 21 30	0.00	0.00
3 21 60	0.00	0.00
3 22 30	0.00	0.00

5129.
5236.
7063.
9332.
12279.
15734.
19253.
22340.
24478.
25292.
24552.
22510.
19854.
17030.
14232.
11649.
9449.
7074.
6243.
5089.
4157.
3405.
2796.
2301.
1892.
1567.
1286.
1057.
869.
717.
590.
488.
374.
263.
241.
208.
185.
167.
165.
164.
163.
163.
162.
162.
161.
161.
161.
161.
161.
164.
173.
168.
206.
223.
235.
238.
233.
222.
210.
200.
193.
186.
181.
177.

1	4 00	0.00	0.00	160.
1	5 30	0.00	0.00	160.
1	5 60	0.00	0.00	160.
1	6 30	0.01	0.00	160.
1	6 60	0.01	0.00	160.
1	7 30	0.01	0.00	160.
1	7 60	0.01	0.00	160.
1	8 30	0.01	0.00	160.
1	8 60	0.01	0.00	160.
1	9 30	0.01	0.00	160.
1	9 60	0.01	0.00	160.
1	10 30	0.01	0.00	161.
1	10 60	0.01	0.00	161.
1	11 30	0.01	0.00	161.
1	11 60	0.01	0.00	161.
1	12 30	0.05	0.00	161.
1	12 60	0.05	0.00	161.
1	13 30	0.06	0.00	161.
1	13 60	0.06	0.00	161.
1	14 30	0.07	0.00	161.
1	14 60	0.07	0.00	162.
1	15 30	0.18	0.00	162.
1	15 60	0.18	0.10	178.
1	16 30	0.07	0.00	219.
1	16 60	0.07	0.00	272.
1	17 30	0.05	0.00	328.
1	17 60	0.05	0.00	374.
1	18 30	0.01	0.00	397.
1	18 60	0.01	0.00	395.
1	19 30	0.01	0.00	366.
1	19 60	0.01	0.00	326.
1	20 30	0.01	0.00	294.
1	20 60	0.01	0.00	269.
1	21 30	0.01	0.00	240.
1	21 60	0.01	0.00	231.
1	22 30	0.01	0.00	217.
1	22 60	0.01	0.00	206.
1	23 30	0.01	0.00	197.
1	23 60	0.01	0.00	190.
2	0 30	0.05	0.00	184.
2	0 60	0.05	0.00	180.
2	1 30	0.05	0.00	176.
2	1 60	0.05	0.00	174.
2	2 30	0.05	0.00	171.
2	2 60	0.05	0.00	170.
2	3 30	0.05	0.00	169.
2	3 60	0.05	0.00	168.
2	4 30	0.05	0.00	167.
2	4 60	0.05	0.00	166.
2	5 30	0.05	0.00	166.
2	5 60	0.05	0.00	166.
2	6 30	0.15	0.07	174.
2	6 60	0.15	0.07	213.
2	7 30	0.15	0.07	289.
2	7 60	0.15	0.07	404.
2	8 30	0.15	0.07	551.
2	8 60	0.15	0.07	715.
2	9 30	0.15	0.07	877.
2	9 60	0.15	0.07	1018.
2	10 30	0.15	0.07	1133.
2	10 60	0.15	0.07	1225.
2	11 30	0.15	0.07	1299.
2	11 60	0.15	0.07	1359.
2	12 30	0.78	0.70	1501.
2	12 60	0.78	0.70	1880.
2	13 30	0.93	0.86	2602.

 NEC-1 VERSION DATED JAN 1973
 UPDATED AUG 74
 CHANGE NO. 01

SPILLWAY DESIGN FLOOD
 PARAN LAKE DAM
 PHASE I DAM SAFETY INVESTIGATION

JOB SPECIFICATION
 NQ NHR NMN IDAY IHR IMIN METRC IPLT IPRT NSTAN
 144 0 30 1 0 0 0 2 0 0
 JOPER NWT
 3 0

 SUB-AREA RUNOFF COMPUTATION

PROBABLE MAXIMUM 24-HOUR PRECIPITATION
 ISTAQ ICOMP IECON ITAPE JPLT JPRT INAME
 1 0 0 0 0 0 1

HYDROGRAPH DATA
 IHYDG IUHG TAREA SNAP TRSDA TRSPC RATIO ISNOW ISAME LOCAL
 1 1 15.60 0.0 15.60 0.0 0.500 0 0 0

PRECIP DATA
 SPFE PHS R6 R12 R24 R48 R72 R96
 0.0 18.00 106.00 118.00 129.00 137.00 141.00 0.0
 TRSPC COMPUTED BY THE PROGRAM IS 0.815

LOSS DATA
 STRKR DLTKR RTIOL ERAIN STPKS RTIOK STRTL CNSTL ALSHX RTIMP
 0.0 0.0 1.00 0.0 0.0 1.00 0.70 0.15 0.0 0.00


UNIT HYDROGRAPH DATA
 TPF 3.00 CP#0.68 NTAF 0


RECESSION DATA
 STRTO# 160.00 QRESN# 160.00 RTIOF# 1.00
 APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE TCA 7.01 AND RA 4.67 INTERVALS

UNIT HYDROGRAPH 29 END-OF-PERIOD ORDINATES, LAG# 2.99 HOURS, CP# 0.67 VOL# 1.00
 148. 539. 1057. 1636. 2048. 2776. 2258. 1971. 1590. 1282.
 1034. 834. 673. 543. 438. 353. 285. 230. 185. 149.
 121. 97. 78. 63. 51. 41. 33. 27. 22.

END-OF-PERIOD FLOW

TIME	RAIN	EXCS	COMP Q
1 0 30	0.00	0.00	160.
1 0 60	0.00	0.00	160.
1 1 30	0.00	0.00	160.
1 1 60	0.00	0.00	160.
1 2 30	0.00	0.00	160.
1 2 60	0.00	0.00	160.
1 3 30	0.00	0.00	160.
1 3 60	0.00	0.00	160.
1 4 30	0.00	0.00	160.





DUFRESNE-HENRY ENGINEERING CORPORATION

BY _____ SUBJECT _____ SHEET NO. _____ OF _____
 DATE _____ JOB NO. _____

Total Q

Shovel	Pipe	W.C. in	Day	Total
647	= 365	+ 0		= 365
648	= 390	+ 425		= 815
649	= 400	+ 1075		= 1475
650	= 420	+ 1700		= 2120
651	= 435	+ 2190	+ 750	= 3365
652	= 450	+ 2610	+ 2850	= 5910
653	= 465	+ 3000	+ 6600	= 10065
654	= 480	+ 3450	+ 11100	= 15030

UNITARY PRINTOUT FOR MULTIPLE PROFILES

AT: G CURVE

SECTION NUMBER	CHANNEL LENGTH	MIN EL OF ROADWAY	MAX EL OF LOW CHORD	MIN EL OF GROUND	DISCHARGE XCFSC	CWSEL	CRWS	EG	TOPWID	10X+S	TIME	VOL
1.00	0.0	0.0	0.0	641.80	3500.00	648.56	648.56	651.97	35.08	14.15	0.0	0.0
1.00	0.0	0.0	0.0	641.80	4000.00	649.20	649.20	652.91	35.10	13.93	0.0	0.0
1.00	0.0	0.0	0.0	641.80	4500.00	649.79	649.79	653.82	35.10	13.94	0.0	0.0
1.00	0.0	0.0	0.0	641.80	5000.00	650.37	650.37	654.69	35.10	13.86	0.0	0.0
2.10	29.00	0.0	0.0	641.80	3500.00	653.89	0.0	653.97	140.00	0.13	0.00	0.41
2.10	29.00	0.0	0.0	641.80	4000.00	655.01	0.0	655.09	140.00	0.12	0.00	0.45
2.10	29.00	0.0	0.0	641.80	4500.00	656.10	0.0	656.19	140.00	0.12	0.00	0.47
2.10	29.00	0.0	0.0	641.80	5000.00	657.14	0.0	657.23	140.00	0.11	0.00	0.53
2.20	1.00	646.80	0.0	644.30	3500.00	654.13	0.0	654.27	140.00	0.33	0.00	0.44
2.20	1.00	646.80	0.0	644.30	4000.00	655.26	0.0	655.41	140.00	0.29	0.00	0.47
2.20	1.00	646.80	0.0	644.30	4500.00	656.37	0.0	656.52	140.00	0.26	0.00	0.50
2.20	1.00	646.80	0.0	644.30	5000.00	657.43	0.0	657.58	140.00	0.23	0.00	0.57

SECTION NUMBER	DISCHARGE CFS	CWSEL	CWSEL DIFF EACH Q	CWSEL DIFF EACH SECTION	CWSEL-MSELK	TOPWID	T.W. DIFF	LENGTH
1.000	3500.000	648.560	0.0	0.0	0.0	35.080	0.0	0.0
1.000	4000.000	649.203	0.643	0.0	0.0	35.097	-0.017	0.0
1.000	4500.000	649.785	0.583	0.0	0.0	35.100	-0.020	0.0
1.000	5000.000	650.366	0.581	0.0	0.0	35.100	-0.020	0.0
2.100	3500.000	653.891	0.0	5.331	0.0	140.001	0.0	29.000
2.100	4000.000	655.008	1.117	5.805	0.0	140.001	-0.000	29.000
2.100	4500.000	656.100	1.092	6.314	0.0	140.001	-0.000	29.000
2.100	5000.000	657.141	1.041	6.774	0.0	140.002	-0.001	29.000
2.200	3500.000	654.130	0.0	0.239	0.0	140.001	0.0	1.000
2.200	4000.000	655.264	1.134	0.256	0.0	140.001	-0.000	1.000
2.200	4500.000	656.371	1.107	0.271	0.0	140.001	-0.000	1.000
2.200	5000.000	657.428	1.057	0.288	0.0	140.002	-0.001	1.000

DATA FOR LAST CROSS SECTION

PROFILE	TYPE	ENC	TARGET	TOP WIDTH AREA-ACRES	TOP WIDTH AREA-DIFF
1	0.0	0.0	0.0	0.045	0.0
2	0.0	0.0	0.0	0.045	0.000
3	0.0	0.0	0.0	0.045	0.000
4	0.0	0.0	0.0	0.045	0.000

2.100	1000.000	646.928	1.934	2.197	0.0	90.000	0.0	29.000
2.100	1500.000	648.539	1.611	2.894	0.0	90.000	0.0	29.000
2.100	2000.000	650.125	1.586	3.672	0.0	140.000	-50.000	29.000
2.100	2500.000	651.453	1.328	4.241	0.0	140.000	-50.000	29.000
2.100	3000.000	652.709	1.257	4.811	0.0	140.001	-50.001	29.000
2.200	50.000	647.091	0.0	4.080	0.0	89.970	0.0	1.000
2.200	100.000	647.267	0.176	4.131	0.0	89.974	-0.004	1.000
2.200	200.000	647.545	0.278	4.212	0.0	89.981	-0.011	1.000
2.200	500.000	648.152	0.608	3.159	0.0	89.996	-0.027	1.000
2.200	1000.000	648.913	0.761	1.986	0.0	90.000	-0.030	1.000
2.200	1500.000	649.599	0.886	1.060	0.0	140.000	-50.030	1.000
2.200	2000.000	650.556	0.957	0.431	0.0	140.000	-50.030	1.000
2.200	2500.000	651.710	1.155	0.257	0.0	140.000	-50.031	1.000
2.200	3000.000	652.951	1.241	0.241	0.0	140.001	-50.031	1.000

DATA FOR LAST CROSS SECTION

PROFILE	TYPE ENC	TARGET	TOP WIDTH AREA-ACRES	TOP WIDTH AREA-DIFF
1	0.0	0.0	0.044	0.0
2	0.0	0.0	0.044	0.000
3	0.0	0.0	0.044	0.000
4	0.0	0.0	0.044	0.000
5	0.0	0.0	0.044	0.000
6	0.0	0.0	0.044	0.001
7	0.0	0.0	0.045	0.001
8	0.0	0.0	0.045	0.001
9	0.0	0.0	0.045	0.001

SUMMARY PRINTOUT FOR MULTIPLE PROFILES

RATING CURVE

SEC NUM	ON R	CHANNEL LENGTH	MIN EL OF ROADWAY	MAX EL OF LOW CHORD	MIN EL GROUND	DISCHARGE SCFS	CWSEL	CRIMS	EG	TOPWID	10K+S	TIME	VOL
→ 1.00		0.0	0.0	0.0	641.80	50.00	642.20	642.20	642.40	34.91	28.95	0.0	0.0
1.00		0.0	0.0	0.0	641.80	100.00	642.43	642.43	642.75	34.92	25.33	0.0	0.0
1.00		0.0	0.0	0.0	641.80	200.00	642.80	642.80	643.31	34.93	21.96	0.0	0.0
1.00		0.0	0.0	0.0	641.80	500.00	643.64	643.64	644.58	34.95	18.69	0.0	0.0
1.00		0.0	0.0	0.0	641.80	1000.00	644.73	644.73	646.21	34.96	16.51	0.0	0.0
1.00		0.0	0.0	0.0	641.80	1500.00	645.64	645.64	647.58	35.00	15.51	0.0	0.0
1.00		0.0	0.0	0.0	641.80	2000.00	646.45	646.45	648.80	35.02	15.00	0.0	0.0
1.00		0.0	0.0	0.0	641.80	2500.00	647.21	647.21	649.93	35.04	14.51	0.0	0.0
1.00		0.0	0.0	0.0	641.80	3000.00	647.90	647.90	650.98	35.06	14.35	0.0	0.0
2.10		29.00	0.0	0.0	642.80	50.00	643.01	643.01	643.12	90.00	35.75	0.00	0.01
2.10		29.00	0.0	0.0	642.80	100.00	643.14	643.14	643.30	90.00	30.40	0.00	0.02
2.10		29.00	0.0	0.0	642.80	200.00	643.33	643.33	643.60	90.00	26.12	0.00	0.03
2.10		29.00	0.0	0.0	642.80	500.00	644.99	643.78	645.09	90.00	1.48	0.00	0.05
2.10		29.00	0.0	0.0	642.80	1000.00	646.93	0.0	647.04	90.00	0.71	0.00	0.16
2.10		29.00	0.0	0.0	642.80	1500.00	648.54	0.0	648.67	90.00	0.54	0.00	0.22
2.10		29.00	0.0	0.0	642.80	2000.00	650.12	0.0	650.16	140.00	0.16	0.00	0.27
2.10		29.00	0.0	0.0	642.80	2500.00	651.45	0.0	651.52	140.00	0.15	0.00	0.31
2.10		29.00	0.0	0.0	642.80	3000.00	652.71	0.0	652.78	140.00	0.14	0.00	0.34
2.20		1.00	646.80	0.0	644.30	50.00	647.09	0.0	647.09	89.97	0.01	0.00	0.01
2.20		1.00	646.80	0.0	644.30	100.00	647.27	0.0	647.27	89.97	0.02	0.00	0.02
2.20		1.00	646.80	0.0	644.30	200.00	647.54	0.0	647.55	89.96	0.07	0.00	0.03
2.20		1.00	646.80	0.0	644.30	500.00	648.15	0.0	648.18	90.00	0.24	0.00	0.07
2.20		1.00	646.80	0.0	644.30	1000.00	648.91	0.0	649.00	90.00	0.53	0.00	0.17
2.20		1.00	646.80	0.0	644.30	1500.00	649.60	0.0	649.73	140.00	0.66	0.00	0.23
2.20		1.00	646.80	0.0	644.30	2000.00	650.56	0.0	650.71	140.00	0.62	0.00	0.29
2.20		1.00	646.80	0.0	644.30	2500.00	651.71	0.0	651.86	140.00	0.50	0.00	0.35
2.20		1.00	646.80	0.0	644.30	3000.00	652.95	0.0	653.10	140.00	0.40	0.00	0.40
SECTION NUMBER	DISCHARGE CFS	CWSEL	CWSEL DIFF EACH 0	CWSEL DIFF EACH SECTION	CWSEL-MSELK	TOPWID	T.W. DIFF	LENGTH					
1.000	50.000	642.199	0.0	0.0	0.0	34.911	0.0	0.0					
1.000	100.000	642.431	0.232	0.0	0.0	34.917	-0.006	0.0					
1.000	200.000	642.803	0.372	0.0	0.0	34.927	-0.016	0.0					
1.000	500.000	643.642	0.838	0.0	0.0	34.949	-0.038	0.0					
1.000	1000.000	644.730	1.089	0.0	0.0	34.978	-0.068	0.0					
1.000	1500.000	645.645	0.914	0.0	0.0	35.003	-0.092	0.0					
1.000	2000.000	646.452	0.808	0.0	0.0	35.024	-0.113	0.0					
1.000	2500.000	647.212	0.760	0.0	0.0	35.044	-0.134	0.0					
1.000	3000.000	647.899	0.687	0.0	0.0	35.063	-0.152	0.0					
2.100	50.000	643.011	0.0	0.812	0.0	90.000	0.0	29.000					
2.100	100.000	643.136	0.125	0.705	0.0	90.000	0.0	29.000					
2.100	200.000	643.333	0.197	0.530	0.0	90.000	0.0	29.000					
2.100	500.000	644.993	1.660	1.352	0.0	90.000	0.0	29.000					

DUFRESNE-HENRY ENGINEERING CORPORATION

BY _____ SUBJECT Rating Curve for Weir at Lake SHEET NO. _____ OF _____
 DATE _____ D. PARSON JOB NO. _____

Lake Elevation	Discharge
647.1	50
647.3	100
647.5	200
648.2	500
648.9	1000
649.6	1500
650.6	2000
651.7	2500
653.	3000
654.1	3500
655.3	4000
656.4	4500
657.4	5000

NOTE: This analysis was performed by means of the HEC-2 computer program. Analysis takes into account weir submergence by the formation of a standing wave at the constriction in the flume. Another HEC-2 run was prepared to check for obstruction by the Rutland Railroad bridge which does not pose a hazard.

DUFRESNE-HENRY ENGINEERING CORPORATION

BY EJ Shur
DATE 07/10/78

SUBJECT Rating Curve for Outlet Gate
Lake Pecos

SHEET NO. _____ OF _____
JOB NO. _____

Note: data is incomplete for a full analysis of the structure as the detailed plans do not cover the tail of the outlet. Thus it will be assumed that inlet control dominates and also that the actual inlet is the 4' x 5 1/2' box conduit and the gate spanning from 20° wingwalls. All measurements of elevation are based on the assumed lake level of 647±, all calculations are based on Hydraulic Engineering Circular #5, (1965) by the Bureau of Public Roads.

Lake Elevation	Hw/D	Q/B	Q
646	2.7	86	345 cfs
647	2.9	91	365 cfs
648	3.2	97	390 cfs
649	3.4	100	400 cfs
650	3.7	105	420 cfs
651	3.9	109	435 cfs
652	4.2	112	450 cfs
653	4.4	116	465 cfs
654	4.7	120	480 cfs

DUFRESNE-HENRY ENGINEERING CORPORATION

BY EJ (Hajj)

SUBJECT Lake Paros Dam (Rating Curve)

SHEET NO. OF

DATE 07/10/78

JOB NO.

Discharge over the top of the Dam

$$Q = CLH^{3/2} \Rightarrow CAH^{1/2}$$

Lake Elevation	Weir Length (L)	Area (A)	Head (H)	C	Q
650.5	335'	111 sq ft	0.33	3.	190 cfs
651.0	440'	302 sq ft	0.69	3.	750 cfs
651.5	515'	552 sq ft	1.07	3.	1715 cfs
652	597'	833 sq ft	1.4	3.	2950 cfs
652.5	597'	1132 sq ft	1.9	3.	4675 cfs
653	597	1430 sq ft	2.4	3.	6640 cfs
653.5	597	1729 sq ft	2.9	3.	8830 cfs
654	597	2027 sq ft	3.4	3.	11205 cfs
654.5	597	2325 sq ft	3.9	3.	13770 cfs
655.	597	2624 sq ft	4.4	3.	16505 cfs
655.5	597	2923 sq ft	4.9	3.	19400 cfs
656	597	3221 sq ft	5.4	3.	22445 cfs
656.5	597	3520 sq ft	5.9	3.	25640 cfs

[illegible]

[illegible]

—

RUNOFF MULTIPLIED BY 0.50									
80.	80.	80.	80.	80.	80.	80.	80.	80.	80.
80.	80.	80.	80.	80.	80.	80.	80.	80.	80.
80.	80.	80.	80.	80.	80.	80.	80.	80.	80.
81.	89.	109.	136.	164.	187.	199.	198.	183.	163.
147.	134.	124.	115.	109.	103.	99.	95.	92.	90.
88.	87.	86.	85.	84.	84.	84.	83.	83.	83.
87.	106.	144.	202.	276.	357.	438.	509.	566.	612.
449.	679.	750.	940.	1301.	1862.	2618.	3532.	4666.	6139.
7867.	9626.	11170.	12239.	12646.	12276.	11255.	9927.	8515.	7116.
5825.	4725.	3837.	3122.	2544.	2079.	1703.	1398.	1151.	949.
784.	643.	529.	434.	358.	295.	244.	187.	141.	121.
104.	93.	83.	83.	82.	82.	81.	81.	81.	81.
81.	80.	80.	80.	80.	80.	82.	86.	94.	103.
112.	117.	119.	116.	111.	105.	100.	96.	93.	91.
89.	87.	86.	85.						
CFS		PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME			
INCHES		12646.	9550.	3332.	1174.	169114.			
AC-FT			5.69	7.95	8.40	8.40			
			4738.	6613.	6992.	6992.			

STATION 1

[illegible]

[illegible]

3 1	601
3 1	301
3 14	601
3 15	301
3 1	601
3 1	301
3 1	60.
3 17	30.
3 17	60.
3 1	30.
3 1	60.
3 1	30.
3 19	60.
3 20	30.
3 2	601
3 2	301
3 2	601
3 22	301
3 22	601
3 2	301
3 2	601

1. 2. 3. 4. 5. 6. 7. 8. 9. 10. 11. 12. 13. 14. 15. 16. 17. 18. 19. 20. 21. 22. 23. 24. 25. 26. 27. 28. 29. 30. 31. 32. 33. 34. 35. 36. 37. 38. 39. 40. 41. 42. 43. 44. 45. 46. 47. 48. 49. 50. 51. 52. 53. 54. 55. 56. 57. 58. 59. 60. 61. 62. 63. 64. 65. 66. 67. 68. 69. 70. 71. 72. 73. 74. 75. 76. 77. 78. 79. 80. 81. 82. 83. 84. 85. 86. 87. 88. 89. 90. 91. 92. 93. 94. 95. 96. 97. 98. 99. 100. 101. 102. 103. 104. 105. 106. 107. 108. 109. 110. 111. 112. 113. 114. 115. 116. 117. 118. 119. 120. 121. 122. 123. 124. 125. 126. 127. 128. 129. 130. 131. 132. 133. 134. 135. 136. 137. 138. 139. 140. 141. 142. 143. 144. 145. 146. 147. 148. 149. 150. 151. 152. 153. 154. 155. 156. 157. 158. 159. 160. 161. 162. 163. 164. 165. 166. 167. 168. 169. 170. 171. 172. 173. 174. 175. 176. 177. 178. 179. 180. 181. 182. 183. 184. 185. 186. 187. 188. 189. 190. 191. 192. 193. 194. 195. 196. 197. 198. 199. 200. 201. 202. 203. 204. 205. 206. 207. 208. 209. 210. 211. 212. 213. 214. 215. 216. 217. 218. 219. 220. 221. 222. 223. 224. 225. 226. 227. 228. 229. 230. 231. 232. 233. 234. 235. 236. 237. 238. 239. 240. 241. 242. 243. 244. 245. 246. 247. 248. 249. 250. 251. 252. 253. 254. 255. 256. 257. 258. 259. 260. 261. 262. 263. 264. 265. 266. 267. 268. 269. 270. 271. 272. 273. 274. 275. 276. 277. 278. 279. 280. 281. 282. 283. 284. 285. 286. 287. 288. 289. 290. 291. 292. 293. 294. 295. 296. 297. 298. 299. 300. 301. 302. 303. 304. 305. 306. 307. 308. 309. 310. 311. 312. 313. 314. 315. 316. 317. 318. 319. 320. 321. 322. 323. 324. 325. 326. 327. 328. 329. 330. 331. 332. 333. 334. 335. 336. 337. 338. 339. 340. 341. 342. 343. 344. 345. 346. 347. 348. 349. 350. 351. 352. 353. 354. 355. 356. 357. 358. 359. 360. 361. 362. 363. 364. 365. 366. 367. 368. 369. 370. 371. 372. 373. 374. 375. 376. 377. 378. 379. 380. 381. 382. 383. 384. 385. 386. 387. 388. 389. 390. 391. 392. 393. 394. 395. 396. 397. 398. 399. 400. 401. 402. 403. 404. 405. 406. 407. 408. 409. 410. 411. 412. 413. 414. 415. 416. 417. 418. 419. 420. 421. 422. 423. 424. 425. 426. 427. 428. 429. 430. 431. 432. 433. 434. 435. 436. 437. 438. 439. 440. 441. 442. 443. 444. 445. 446. 447. 448. 449. 450. 451. 452. 453. 454. 455. 456. 457. 458. 459. 460. 461. 462. 463. 464. 465. 466. 467. 468. 469. 470. 471. 472. 473. 474. 475. 476. 477. 478. 479. 480. 481. 482. 483. 484. 485. 486. 487. 488. 489. 490. 491. 492. 493. 494. 495. 496. 497. 498. 499. 500. 501. 502. 503. 504. 505. 506. 507. 508. 509. 510. 511. 512. 513. 514. 515. 516. 517. 518. 519. 520. 521. 522. 523. 524. 525. 526. 527. 528. 529. 530. 531. 532. 533. 534. 535. 536. 537. 538. 539. 540. 541. 542. 543. 544. 545. 546. 547. 548. 549. 550. 551. 552. 553. 554. 555. 556. 557. 558. 559. 560. 561. 562. 563. 564. 565. 566. 567. 568. 569. 570. 571. 572. 573. 574. 575. 576. 577. 578. 579. 580. 581. 582. 583. 584. 585. 586. 587. 588. 589. 590. 591. 592. 593. 594. 595. 596. 597. 598. 599. 600. 601. 602. 603. 604. 605. 606. 607. 608. 609. 610. 611. 612. 613. 614. 615. 616. 617. 618. 619. 620. 621. 622. 623. 624. 625. 626. 627. 628. 629. 630. 631. 632. 633. 634. 635. 636. 637. 638. 639. 640. 641. 642. 643. 644. 645. 646. 647. 648. 649. 650. 651. 652. 653. 654. 655. 656. 657. 658. 659. 660. 661. 662. 663. 664. 665. 666. 667. 668. 669. 670. 671. 672. 673. 674. 675. 676. 677. 678. 679. 680. 681. 682. 683. 684. 685. 686. 687. 688. 689. 690. 691. 692. 693. 694. 695. 696. 697. 698. 699. 700. 701. 702. 703. 704. 705. 706. 707. 708. 709. 710. 711. 712. 713. 714. 715. 716. 717. 718. 719. 720. 721. 722. 723. 724. 725. 726. 727. 728. 729. 730. 731. 732. 733. 734. 735. 736. 737. 738. 739. 740. 741. 742. 743. 744. 745. 746. 747. 748. 749. 750. 751. 752. 753. 754. 755. 756. 757. 758. 759. 760. 761. 762. 763. 764. 765. 766. 767. 768. 769. 770. 771. 772. 773. 774. 775. 776. 777. 778. 779. 780. 781. 782. 783. 784. 785. 786. 787. 788. 789. 790. 791. 792. 793. 794. 795. 796. 797. 798. 799. 800. 801. 802. 803. 804. 805. 806. 807. 808. 809. 810. 811. 812. 813. 814. 815. 816. 817. 818. 819. 820. 821. 822. 823. 824. 825. 826. 827. 828. 829. 830. 831. 832. 833. 834. 835. 836. 837. 838. 839. 840. 84

| | | |
|---|---|-----|
| 1 | 1 | 601 |
| 1 | 1 | 301 |

1-14 601

15 301

1 1 601
1 2 601

| | | |
|---|---|-----|
| 5 | 1 | 301 |
| 2 | 1 | 60 |

9 17 30.

17 60.

3 1 30.

3 1 60.
3 1 30.

3 19 60.

3 20 30.

3 2 601
3 1 301

3 2 301
3 2 601

3 22 301

3 22 601

3 2 301
3 2 301

HYDROGRAPH ROUTING

PULS RESERVOIR ROUTING

ISTAQ 1 ICOMP 1 IECON 0 ITAPE 0 JPLT 0 JPRT 0 INAME 1

ROUTING DATA
QLOSS 0.0 CLOSS 0.0 AVG 0.0 IRES 1 ISAME 0

NSTPS 0 NSTDL 0 LAG 0 AMSKK 0.0 X 0.0 TSK 0.0 STORA -1.

ORAGE# 252. 259. 295. 331. 367. 403. 439. 475. 496. 511.
IFLOW# 0. 365. 615. 1475. 2120. 3365. 5910. 10065. 13500. 15030.

TIME EOP STOR AVG IN EOP OUT

| | | | |
|---------|------|------|------|
| 1 0 30 | 254. | 80. | 80. |
| 1 0 60 | 254. | 80. | 80. |
| 1 1 30 | 254. | 80. | 80. |
| 1 1 60 | 254. | 80. | 80. |
| 1 2 30 | 254. | 80. | 80. |
| 1 2 60 | 254. | 80. | 80. |
| 1 3 30 | 254. | 80. | 80. |
| 1 3 60 | 254. | 80. | 80. |
| 1 4 30 | 254. | 80. | 80. |
| 1 4 60 | 254. | 80. | 80. |
| 1 5 30 | 254. | 80. | 80. |
| 1 5 60 | 254. | 80. | 80. |
| 1 6 30 | 254. | 80. | 80. |
| 1 6 60 | 254. | 80. | 80. |
| 1 7 30 | 254. | 80. | 80. |
| 1 7 60 | 254. | 80. | 80. |
| 1 8 30 | 254. | 80. | 80. |
| 1 8 60 | 254. | 80. | 80. |
| 1 9 30 | 254. | 80. | 80. |
| 1 9 60 | 254. | 80. | 80. |
| 1 10 30 | 254. | 80. | 80. |
| 1 10 60 | 254. | 80. | 80. |
| 1 11 30 | 254. | 80. | 80. |
| 1 11 60 | 254. | 80. | 80. |
| 1 12 30 | 254. | 80. | 80. |
| 1 12 60 | 254. | 80. | 80. |
| 1 13 30 | 254. | 80. | 80. |
| 1 13 60 | 254. | 80. | 80. |
| 1 14 30 | 254. | 81. | 81. |
| 1 14 60 | 254. | 81. | 81. |
| 1 15 30 | 254. | 81. | 81. |
| 1 15 60 | 254. | 85. | 85. |
| 1 16 30 | 254. | 99. | 100. |
| 1 16 60 | 254. | 123. | 124. |
| 1 17 30 | 255. | 150. | 151. |
| 1 17 60 | 255. | 176. | 176. |
| 1 18 30 | 256. | 193. | 193. |
| 1 18 60 | 256. | 198. | 198. |
| 1 19 30 | 256. | 190. | 190. |
| 1 19 60 | 255. | 173. | 172. |

| | | | |
|---------|------|--------|--------|
| 1 20 30 | 255. | 141. | 140. |
| 1 21 30 | 254. | 129. | 129. |
| 1 21 60 | 254. | 120. | 119. |
| 1 22 30 | 254. | 112. | 112. |
| 1 22 60 | 254. | 106. | 106. |
| 1 23 30 | 254. | 101. | 101. |
| 1 23 60 | 254. | 97. | 97. |
| 2 0 30 | 254. | 94. | 94. |
| 2 0 60 | 254. | 91. | 91. |
| 2 1 30 | 254. | 89. | 89. |
| 2 1 60 | 254. | 87. | 87. |
| 2 2 30 | 254. | 86. | 86. |
| 2 2 60 | 254. | 85. | 85. |
| 2 3 30 | 254. | 85. | 85. |
| 2 3 60 | 254. | 84. | 84. |
| 2 4 30 | 254. | 84. | 84. |
| 2 4 60 | 254. | 83. | 83. |
| 2 5 30 | 254. | 83. | 83. |
| 2 5 60 | 254. | 83. | 83. |
| 2 6 30 | 254. | 85. | 85. |
| 2 6 60 | 254. | 97. | 97. |
| 2 7 30 | 254. | 125. | 126. |
| 2 7 60 | 255. | 173. | 175. |
| 2 8 30 | 257. | 239. | 241. |
| 2 8 60 | 258. | 317. | 319. |
| 2 9 30 | 260. | 398. | 379. |
| 2 9 60 | 263. | 474. | 418. |
| 2 10 30 | 267. | 538. | 467. |
| 2 10 60 | 271. | 589. | 517. |
| 2 11 30 | 275. | 631. | 564. |
| 2 11 60 | 278. | 664. | 605. |
| 2 12 30 | 282. | 715. | 650. |
| 2 12 60 | 288. | 845. | 730. |
| 2 13 30 | 301. | 1120. | 916. |
| 2 13 60 | 320. | 1581. | 1282. |
| 2 14 30 | 349. | 2240. | 1803. |
| 2 14 60 | 384. | 3075. | 2691. |
| 2 15 30 | 413. | 4099. | 4076. |
| 2 15 60 | 435. | 5403. | 5651. |
| 2 16 30 | 453. | 7003. | 7508. |
| 2 16 60 | 468. | 8747. | 9253. |
| 2 17 30 | 480. | 10398. | 10943. |
| 2 17 60 | 488. | 11704. | 12118. |
| 2 18 30 | 491. | 12443. | 12619. |
| 2 18 60 | 489. | 12461. | 12375. |
| 2 19 30 | 483. | 11765. | 11434. |
| 2 19 60 | 475. | 10591. | 10133. |
| 2 20 30 | 464. | 9221. | 8642. |
| 2 20 60 | 452. | 7816. | 7396. |
| 2 21 30 | 441. | 6470. | 6092. |
| 2 21 60 | 427. | 5275. | 5093. |
| 2 22 30 | 414. | 4281. | 4129. |
| 2 22 60 | 403. | 3479. | 3360. |
| 2 23 30 | 390. | 2833. | 2921. |
| 2 23 60 | 375. | 2311. | 2413. |
| 3 0 30 | 362. | 1891. | 2028. |
| 3 0 60 | 347. | 1550. | 1770. |
| 3 1 30 | 333. | 1274. | 1502. |
| 3 1 60 | 319. | 1050. | 1254. |
| 3 2 30 | 307. | 866. | 1041. |
| 3 2 60 | 298. | 713. | 861. |
| 3 3 30 | 289. | 586. | 736. |
| 3 3 60 | 280. | 481. | 632. |
| 3 4 30 | 273. | 396. | 535. |
| 3 4 60 | 266. | 327. | 450. |

| | | | |
|---------|------|------|------|
| 3 5 30 | 260. | 269. | 370. |
| 3 5 60 | 256. | 216. | 226. |
| 3 6 30 | 255. | 164. | 162. |
| 3 6 60 | 254. | 131. | 130. |
| 3 7 30 | 254. | 112. | 112. |
| 3 7 60 | 254. | 98. | 98. |
| 3 8 30 | 254. | 88. | 88. |
| 3 8 60 | 254. | 83. | 83. |
| 3 9 30 | 254. | 82. | 82. |
| 3 9 60 | 254. | 82. | 82. |
| 3 10 30 | 254. | 82. | 82. |
| 3 10 60 | 254. | 81. | 81. |
| 3 11 30 | 254. | 81. | 81. |
| 3 11 60 | 254. | 81. | 81. |
| 3 12 30 | 254. | 81. | 81. |
| 3 12 60 | 254. | 80. | 80. |
| 3 13 30 | 254. | 80. | 80. |
| 3 13 60 | 254. | 80. | 80. |
| 3 14 30 | 254. | 80. | 80. |
| 3 14 60 | 254. | 80. | 80. |
| 3 15 30 | 254. | 81. | 81. |
| 3 15 60 | 254. | 84. | 84. |
| 3 16 30 | 254. | 90. | 91. |
| 3 16 60 | 254. | 99. | 99. |
| 3 17 30 | 254. | 107. | 108. |
| 3 17 60 | 254. | 114. | 115. |
| 3 18 30 | 254. | 118. | 118. |
| 3 18 60 | 254. | 118. | 118. |
| 3 19 30 | 254. | 114. | 113. |
| 3 19 60 | 254. | 108. | 108. |
| 3 20 30 | 254. | 103. | 102. |
| 3 20 60 | 254. | 98. | 98. |
| 3 21 30 | 254. | 95. | 95. |
| 3 21 60 | 254. | 92. | 92. |
| 3 22 30 | 254. | 90. | 90. |
| 3 22 60 | 254. | 88. | 88. |
| 3 23 30 | 254. | 86. | 86. |
| 3 23 60 | 254. | 85. | 85. |

SUM

169111.

| | | | | | |
|--------|--------|--------|---------|---------|--------------|
| | PEAK | 6-HOUR | 24-HOUR | 72-HOUR | TOTAL VOLUME |
| CFS | 12619. | 9530. | 3332. | 1174. | 169111. |
| INCHES | | 5.68 | 7.95 | 8.40 | 8.40 |
| AC-FT | | 4728. | 6612. | 6992. | 6992. |

r

I

[illegible]


| Line | Address | Hex | Asm | Comment |
|------|---------|-----|-----|---------|
| 1 | 401 | 00 | LDI | |
| 2 | 501 | 00 | LDI | |
| 3 | 601 | 00 | LDI | |
| 4 | 701 | 00 | LDI | |
| 5 | 801 | 00 | LDI | |
| 6 | 901 | 00 | LDI | |
| 7 | 1001 | 00 | LDI | |
| 8 | 1101 | 00 | LDI | |
| 9 | 1201 | 00 | LDI | |
| 10 | 1301 | 00 | LDI | |
| 11 | 1401 | 00 | LDI | |
| 12 | 1501 | 00 | LDI | |
| 13 | 1601 | 00 | LDI | |
| 14 | 1701 | 00 | LDI | |
| 15 | 1801 | 00 | LDI | |
| 16 | 1901 | 00 | LDI | |
| 17 | 2001 | 00 | LDI | |
| 18 | 2101 | 00 | LDI | |
| 19 | 2201 | 00 | LDI | |
| 20 | 2301 | 00 | LDI | |
| 21 | 2401 | 00 | LDI | |
| 22 | 2501 | 00 | LDI | |
| 23 | 2601 | 00 | LDI | |
| 24 | 2701 | 00 | LDI | |
| 25 | 2801 | 00 | LDI | |
| 26 | 2901 | 00 | LDI | |
| 27 | 3001 | 00 | LDI | |
| 28 | 3101 | 00 | LDI | |
| 29 | 3201 | 00 | LDI | |
| 30 | 3301 | 00 | LDI | |
| 31 | 3401 | 00 | LDI | |
| 32 | 3501 | 00 | LDI | |
| 33 | 3601 | 00 | LDI | |
| 34 | 3701 | 00 | LDI | |
| 35 | 3801 | 00 | LDI | |
| 36 | 3901 | 00 | LDI | |
| 37 | 4001 | 00 | LDI | |
| 38 | 4101 | 00 | LDI | |
| 39 | 4201 | 00 | LDI | |
| 40 | 4301 | 00 | LDI | |
| 41 | 4401 | 00 | LDI | |
| 42 | 4501 | 00 | LDI | |
| 43 | 4601 | 00 | LDI | |
| 44 | 4701 | 00 | LDI | |
| 45 | 4801 | 00 | LDI | |
| 46 | 4901 | 00 | LDI | |
| 47 | 5001 | 00 | LDI | |
| 48 | 5101 | 00 | LDI | |
| 49 | 5201 | 00 | LDI | |
| 50 | 5301 | 00 | LDI | |
| 51 | 5401 | 00 | LDI | |
| 52 | 5501 | 00 | LDI | |
| 53 | 5601 | 00 | LDI | |
| 54 | 5701 | 00 | LDI | |
| 55 | 5801 | 00 | LDI | |
| 56 | 5901 | 00 | LDI | |
| 57 | 6001 | 00 | LDI | |
| 58 | 6101 | 00 | LDI | |
| 59 | 6201 | 00 | LDI | |
| 60 | 6301 | 00 | LDI | |
| 61 | 6401 | 00 | LDI | |
| 62 | 6501 | 00 | LDI | |
| 63 | 6601 | 00 | LDI | |
| 64 | 6701 | 00 | LDI | |
| 65 | 6801 | 00 | LDI | |
| 66 | 6901 | 00 | LDI | |
| 67 | 7001 | 00 | LDI | |
| 68 | 7101 | 00 | LDI | |
| 69 | 7201 | 00 | LDI | |
| 70 | 7301 | 00 | LDI | |
| 71 | 7401 | 00 | LDI | |
| 72 | 7501 | 00 | LDI | |
| 73 | 7601 | 00 | LDI | |
| 74 | 7701 | 00 | LDI | |
| 75 | 7801 | 00 | LDI | |
| 76 | 7901 | 00 | LDI | |
| 77 | 8001 | 00 | LDI | |
| 78 | 8101 | 00 | LDI | |
| 79 | 8201 | 00 | LDI | |
| 80 | 8301 | 00 | LDI | |
| 81 | 8401 | 00 | LDI | |
| 82 | 8501 | 00 | LDI | |
| 83 | 8601 | 00 | LDI | |
| 84 | 8701 | 00 | LDI | |
| 85 | 8801 | 00 | LDI | |
| 86 | 8901 | 00 | LDI | |
| 87 | 9001 | 00 | LDI | |
| 88 | 9101 | 00 | LDI | |
| 89 | 9201 | 00 | LDI | |
| 90 | 9301 | 00 | LDI | |
| 91 | 9401 | 00 | LDI | |
| 92 | 9501 | 00 | LDI | |
| 93 | 9601 | 00 | LDI | |
| 94 | 9701 | 00 | LDI | |
| 95 | 9801 | 00 | LDI | |
| 96 | 9901 | 00 | LDI | |
| 97 | 10001 | 00 | LDI | |
| 98 | 10101 | 00 | LDI | |
| 99 | 10201 | 00 | LDI | |
| 100 | 10301 | 00 | LDI | |
| 101 | 10401 | 00 | LDI | |
| 102 | 10501 | 00 | LDI | |
| 103 | 10601 | 00 | LDI | |
| 104 | 10701 | 00 | | |

| | | |
|---|----|-----|
| 1 | 13 | 601 |
| 1 | 1 | 301 |
| 1 | 1 | 601 |
| 1 | 1 | 301 |
| 1 | 15 | 601 |
| 1 | 16 | 301 |
| 1 | 1 | 601 |
| 1 | 1 | 30. |
| 1 | 1 | 60. |
| 1 | 18 | 30. |
| 1 | 18 | 60. |
| 1 | 1 | 30. |
| 1 | 1 | 60. |
| 1 | 2 | 30. |
| 1 | 20 | 601 |
| 1 | 21 | 301 |
| 1 | 2 | 601 |
| 1 | 2 | 301 |
| 1 | 2 | 601 |
| 1 | 23 | 301 |
| 1 | 23 | 601 |

[illegible]

RUNOFF SUMMARY, AVERAGE FLOW

| | | PEAK | 6-HOUR | 24-HOUR | 72-HOUR | AREA |
|---------------|---|--------|--------|---------|---------|-------|
| HYDROGRAPH AT | 1 | 12646. | 9550. | 3332. | 1174. | 15.60 |
| ROUTED TO | 1 | 12619. | 9530. | 3332. | 1174. | 15.60 |



AD-A156 743

NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
LAKE PARAM (VT 00006)...(U) CORPS OF ENGINEERS WALTHAM
MA NEW ENGLAND DIV AUG 78


2/2


UNCLASSIFIED

F/G 13/13


NL








10



**BENNINGTON, VERMONT
1975**

U.S. GEOLOGICAL SURVEY
WASHINGTON, D.C. 20506



- Scale 1:50,000
- LEGEND**
- National Forest Boundary
 - U.S. Highway
 - State Highway
 - Railroad
 - Private Road
 - Trail
 - Long Trail and Applicable Trail Locations as of September 1, 1975
 - National Forest Land as of September 1, 1975
 - Forest Supervisor's Headquarters, Bennington, Vermont

Notes:

1. This map is a reproduction of the original map. It is not a survey map. It is a reproduction of a map that was prepared by the U.S. Geological Survey. The map is a reproduction of a map that was prepared by the U.S. Geological Survey. The map is a reproduction of a map that was prepared by the U.S. Geological Survey.

2. This map is a reproduction of the original map. It is not a survey map. It is a reproduction of a map that was prepared by the U.S. Geological Survey. The map is a reproduction of a map that was prepared by the U.S. Geological Survey. The map is a reproduction of a map that was prepared by the U.S. Geological Survey.

3. This map is a reproduction of the original map. It is not a survey map. It is a reproduction of a map that was prepared by the U.S. Geological Survey. The map is a reproduction of a map that was prepared by the U.S. Geological Survey. The map is a reproduction of a map that was prepared by the U.S. Geological Survey.

APPENDIX E

Information as contained in the National Inventory of Dams

DATE
FILMED
-8